

# **ESTIMATION & COST EVALUATION -I**

3<sup>RD</sup> SEM. CIVIL ENGINEERING

STRICTLY ACCORDING TO SCTE&VTSYLLABUS

DEPARTMENT OF CIVIL ENGINEERING  
PREPARED BY: SATYANARAYAN BHUSAGAR

**SCTE&VT SYLLABUS 2021-2022**

<b>Chapter</b>	<b>Name of topics</b>	<b>Hours</b>
<b>1</b>	<b>Introduction :</b>	<b>02</b>
<b>2</b>	<b>Quantity Estimate of Building</b>	<b>30</b>
<b>3</b>	<b>Analysis of Rates and Valuation.</b>	<b>22</b>
<b>4</b>	<b>Administrative Set-Up of Engineering Organisations</b>	<b>04</b>

Estimate: Before undertaking the construction of a project it is necessary to know its probable cost which is worked out by estimating.

An estimate is a computation or calculation of the quantities required and expenditure likely to be incurred in the construction of a work.

The primary object of the estimate is to enable one to know before hand, the cost of the work. The estimate is the probable cost of a work and is determined theoretically by mathematical calculations based on the plans and drawing and current rates. Approximate estimate may be prepared by various methods but accurate estimate is prepared by Detailed estimate method.

Actual cost: The actual cost of a work is known at the completion of the work. Amount of all expenditure is maintained by day-to-day during execution of work in the account section and at the end of the completion of work when the account is completed, the actual cost is known. The actual cost should be not differ much from the estimated cost worked out at the beginning.

An estimate is the anticipated or probable cost of a work and is usually prepared before the construction is taken up. Before undertaking any work or project it is necessary to know its probable cost which is obtained or derived by estimating.

### Plinth Area Estimate

A covered built-up area measured at the floor level of any buildings storey or (at the floor level of the building's basement) is called the plinth area. It is the measure of a building's useable area.

It is also known as the built-up area that is the whole area occupied by the building along with external and internal walls. It is usually 10% to 20% higher than the carpet area.

It should be computed for the enclosed area by measuring the external building's dimensions at the floor level. The courtyard and other open areas will not include in the plinth area.

### Floor Area

Floor area of a building is the total area of floor in between walls and consists of floor of all rooms verandahs passage corridors room, entrance halls, kitchen, store, bath and latrine (w.c) etc. Sills of doors and openings are not included in the Floor Area.

Floor Area is equal to plinth area minus area occupied by walls.

For deduction of wall area from plinth area to obtain floor area shall include - (i) Door and other openings in the wall, (ii) Intermediate pillars and supports, (iii) Plaster along walls exceeding 300 sq.m in area, (iv) Flux with which are within wall.

Circulation Area: Circulation area is the floor area of verandahs, passage, corridors, balconies, entrance hall, porches, staircase, etc which are used for movements of persons using the building. The circulation area of any floor shall comprise of the following:-

- (a) Verandahs and balconies, (b) Passages and corridors, (c) Entrance halls,



The circulation area may be divided into two parts (1) Horizontal circulation area and (2) Vertical circulation area.

### Horizontal Circulation Area:

Horizontal area of a building is the area of verandahs, passage, corridors, balconies, porches etc. which are required for the horizontal movement of the users of the building. This may be 40% to 15% of the plinth area of the building.

### Vertical Circulation Area:

Vertical circulation area of a building is the area or space occupied by staircases, lifts and the entrance halls adjacent to them which are required for vertical movement of the users of the building. This may be 4% to 5% of the plinth area of the buildings.

### Carpet Area:

Carpet Area of building is the useable area or liveable area or lettable area. This is the total floor area minus the circulation area, verandahs, corridors, passages, staircase, lifts, entrance hall, etc. and minus other non-useable areas as sanitary accommodations, air conditioner room etc. For office building carpet area is the lettable area or useable area and for residential building carpet area is the liveable area and should exclude the kitchen, pantry, stores and similar other rooms which are not used for living purposes.

### Units of measurements in metric system

#### Units of dimensions for materials and work

<u>Particulars of Materials and Work</u>	<u>Dimensions metric system</u>
1. Bricks, stone blocks, etc.	→ All dimensions cm
2. Tiles, slates, wall board, glass panes, A.C. sheets, sheets etc.	→ Length and breadth in cm or m. → Thickness in mm
3. Doors, windows etc.	→ Height and breadth in cm or m
4. Parts of doors and windows as panels shutters	→ cm or mm
5. Timber	→ Length in m and cross-sectional dimension in cm or mm
6. Masonry (brickwork, stone masonry, etc.)	→ Length and height in m. → Thickness or breadth in cm
7. Cement concrete, Lime concrete, R.C.C. flooring, etc.	→ Length and breadth in m → Thickness in cm
8. White washing, colour washing, Distempers, painting, etc.	→ Length and breadth or height in m.
9. Aggregates, ballast, grit, sand, etc.	→ size in mm
10. Rolled steel sections as I-beam, channel, angle etc.	→ Length in m, section in mm
11. Mild steel bars	→ Length in m, Dia. in mm



Units of measurements and payments for various items of work and materials

Sl No	Particulars of item	Units of measurement in Mks	Units of payment in Mks	Units of payment in FPS
<u>Earthwork</u>				
1.	Earthwork in excavation in ordinary soil	cu.m	per cu.m	1 cu.ft
	earthwork in mixed soil with kankar, baji etc earthwork in hard soil	cu.m	per cu.m	1 cu.ft
2.	Rock excavation	cu.m	per cu.m	1 cu.ft
3.	Earthfilling in excavation in foundation	cu.m	per cu.m	1 cu.ft
4.	Earthfilling in foundation trenches	cu.m	per cu.m	1 cu.ft
5.	Earthfilling in plinth	cu.m	per cu.m	1 cu.ft
6.	Earthwork in banking, cutting in road and irrigation channel	cu.m	per cu.m	1 cu.ft
7.	Surface dressing and levelling, cleaning etc.	sq.m	per sq.m	1 sq.ft
8.	Cutting of trees	no.	per no.	per no.
9.	Puddling, puddle clay core	cu.m	per cu.m	1 cu.ft
10.	Sand filling	cu.m	per cu.m	1 cu.ft
11.	Quarrying of stone or boulders	cu.m	per cu.m	1 cu.ft
12.	Blasting of rock (Blasted stone stacked and then measured)	cu.m	per cu.m	1 cu.ft
<u>Concrete</u>				
1.	Lime concrete in foundation	cu.m	per cu.m	1 cu.ft
2.	Lime concrete in roof terracing, thickness specified	sq.m	per sq.m	1 sq.ft
3.	Cement concrete (C.C)	cu.m	per cu.m	per cu.ft
4.	Reinforced cement concrete (R.C.C)	cu.m	per cu.m	per cu.ft
5.	C.C. or R.C.C. chajja, sunshade	cu.m	per cu.m	per cu.ft
6.	Precast C.C. or R.C.C.	cu.m	per cu.m	per cu.ft
7.	Cement concrete bed	cu.m	per cu.m	per cu.ft
<u>D.P.C</u>				
8.	Damp proof course - cement concrete, Rich cement mortar, Asphalt, etc in cement, lime or mud mortar	sq.m	per sq.m	1 sq.ft
<u>Brickwork</u>				
1.	Brickwork in foundation and plinth, in superstructure, in arches, etc in cement lime or mud mortar	cu.m	per cu.m	1 cu.ft
2.	Sundried brickwork	cu.m	per cu.m	1 cu.ft
3.	Honey-comb brickwork, thickness specified	sq.m	per sq.m	1 sq.ft
4.	Brickwork in jack arches, to be measured separately	cu.m	per cu.m	1 cu.ft
5.	Jack arch roofing including top finishing	sq.m	per sq.m	1 sq.ft
6.	Brickwork in well steining	cu.m	per cu.m	1 cu.ft
7.	Half brickwork with or without reinforcement	sq.m	per sq.m	1 sq.ft
8.	Thin partition wall	sq.m	per sq.m	1 sq.ft



S. No	Particulars of Items	Unit of measurement in mks	Unit of payment in mks	Unit of payment in FPS
8.	Thin partition wall	sq.m	per sq.m	7. sq.ft
9.	Reinforced brickwork (R.B work)	cum	per cum	7. cu.ft
10.	string course, drip course, weather course, coping etc (projection specified)	metre	per m	per ft
11.	cornice	metre	per m	per ft
12.	Brickwork in Fire place, chulla, chimney	cum	per cum	7. cu.ft
13.	Plengeting chimney, fire place blue	metre	per m	per ft
14.	Brick edging	metre	per m	per ft

### Stonework

1.	Stone masonry, Random rubble masonry coursed Rubble masonry, Ashlar masonry, walls, in arches, etc	cum	per cum	7. cu.ft
2.	Cut stone work in lintel, beam etc.	cum	per cum	7. cu.ft
3.	Stone slab in roof, shelves, etc. stone chajja. stone, sun shed etc.	sq.m	per sq.m	7. sq.ft
4.	stonework in wall facing or lining	sq.m	per sq.m	per sq.ft

### Wood work

1.	Wood work, door & window frame or chowkhat, nibbles, beams, roof trusses etc.	cum	per cum	per cu.ft
2.	Door and window shutters or leaves, panelled battens, glazed, part panelled and part glazed wire gauged, etc.	sq.m	per sq.m	per sq.ft
3.	Door and window fittings or hinges, tower bolts, sliding bolts, handles etc.	no.	per no.	per no.
4.	Timbering, boarding (Thickness specified)	sq.m	per sq.m	per sq.ft
5.	Timbering of trenches	sq.m	per sq.m	per sq.ft
6.	Sawing of timber	sq.m	per sq.m	per sq.ft
7.	Woodwork in partition, plywood, etc	sq.m.	per sq.m.	per sq.ft
8.	Balices (Dia. specified)	metre	per m	per ft

### Steel work

1.	Rolled steel joists, channels, Angles, T-irons, Flats, squares, rounds, etc	quintal	per q	per cwt
2.	steel reinforcement bars etc. in RCC. R.B. work	quintal	per q	per cwt
3.	Bending, bending of steel reinforcement	quintal	per q	per cwt
4.	Fabrication and hoisting of steel work	quintal	per q	per cwt
5.	Expanded Metal (X.P.M.) size specified	sq.m	per sq.m	per sq.ft
6.	Fabric reinforcement, wire netting	sq.m	per sq.m	per sq.ft
7.	Iron work in struss	quintal	per q	per cwt
8.	Gusset plate (Min <sup>m</sup> rectangular size from wh. cut)	quintal	per q	per cwt
9.	Cutting of Iron joists, channels	cm	per cm	per inch
10.	Threading in iron	cm	per cm	per inch
11.	cutting angles, T-ees plate	sq.cm	per sq.cm	per sq.in.



12. Welding, solder of sheets, plates	cm	per cm	per inch
13. Boring holes in iron	no.	per no.	per no.
14. Cast Iron (C.I.) pipe, Dia specified	metre	per m	per ft
15. Rivets, Bolts, and nuts, Anchor bolts, Lewis bolts, Holding down bolts, etc.	quintal	per q	per cwt
16. Barbed wire fencing	metre	per m	ft. ft
17. Iron gate	sq. m	per sqm	per sq ft
18. Iron hold fast	quintal	per q	per cwt
19. Iron railing (Height and type spec)	metre	per m	per ft
20. Iron grill, collapsible gate	sq. m	per sqm	per sq ft
21. Steel doors and windows (type & fixing specified)	sq. m	per sqm	per sq ft
22. Steel doors and windows (type and fixing)	sq. m	per sqm	per sq ft

### Roofing

1. Tiled roof - Allahabad tile, Faizabad tile, Mangalore tile etc, including battens	Sqm	per sqm	1. sq ft
2. Country tile roof including bamboo joists	sq. m	per sq m	1. sq ft
3. Corrugated iron (G.I.) roof, Asbestos cement (A.C.) sheet roof	sq. m	per sq. m	1. sq. ft
4. Slate roofing, timber roofing	sq. m	per sq. m	1. sq. ft
5. Mud roof cover and inclusive of tiles or bricks	sq. m	per sqm	1. sq. ft
6. Ridges, valleys, gutters	metre	per m	per ft
7. Expansion, contraction or construction joint	metre	per m	per ft
8. Ceiling - Timber, Ac. sheet, plaster, cloth, cement plaster on XPM, puste board etc.	sq. m	per sq m	per sq ft

### Plastering, pointing and finishing

1. Plastering - cement mortar, lime mortar, mud, etc. (Thickness, proportion specified)	sq. m	per sq. m	1. sq. ft
2. Pointing - struck, Flush, weather etc.	sq. m	per sq m	1. sq ft
3. Dado (Thickness and type specified)	sq. m	per sq. m	1. sq. ft
4. Skirting (Thickness type and height specified)	metre	per m	per ft
5. Cement mortar or lime mortar rubbing	sq. m	per sq. m	1. sq. ft
6. White washing, colour washing, cement washing (No. of coat spec)	sq. m	per sq m	1. sq ft
7. Distemping (No. of coat specified)	sq. m	per sq. m	1. sq. ft
8. Snow cement washing or finishing	sq. m	per sq m	1. sq ft
9. painting, varnishing (No. of coat spec)	sq. m	per sq m	1. sq ft
10. polishing of wood work (No. of coat spec)	sq. m	per sq. m	1. sq. ft
11. painting letters and figure (Ht spec)	no.	per no.	per no.



12. Oiling and clearing of doors and windows	sq.m	per sq.m	7.50/bt
13. Coal Tarring (No. of coat specified)	sq.m	per sq.m	7.50/bt
14. Removing of paint or varnish	sq.m	per sq.m	7.50/bt
15. Goble Lapping (cow dung wash)	sq.m	per sq.m	7.50/bt

### Flooring

1. 2.5cm (1") C.C. over 7.5cm (3") L.C. floor (including L.C.)	sq.m	per sq.m	7.50/bt
2. Conglomerate floor, artificial patent stone floor 2.5cm (1") C.C. over 7.5cm (3") L.C. including L.C.	sq.m	per sq.m	7.50/bt
3. 4cm (1½") thick stone floor flag stone floor over 7.5cm (3") L.C. (including L.C.)	sq.m	per sq.m	7.50/bt
4. 2.5cm (1") marble flooring over 7.5cm (3") L.C. (including L.C.)	sq.m	per sq.m	7.50/bt
5. Mosaic or terrazzo or granolithic floor over 7.5cm (3") L.C. (including L.C.)	sq.m	per sq.m	per sq.ft
6. Brick bat floor over 7.5cm (3") L.C. including L.C.	sq.m	per sq.m	1.50/bt
7. Brick on edge floor over 7.5cm (3") L.C. including	sq.m	per sq.m	7.50/bt
8. 2.5cm (1") or 4cm (1½") G.C. floor	sq.m	per sq.m	7.50/bt
9. Mud flooring finished goble lapping	sq.m	per sq.m	7.50/bt
10. Apron or plinth projection	sq.m	per sq.m	7.50/bt
11. Door and window sill (C.C. or cement mortar plastered)	sq.m	per sq.m	7.50/bt

### Method of building estimate

Ex-1 Estimate the quantities of brickwork and plastering required in a wall 4m long, 3m high and 30cm thick. Calculate also the cost if the rate of brickwork is Rs. 320.00 per cu.m and of plastering is Rs. 2.50 per sq.m.

Ans Quantity of brickwork =  $L \times B \times H = 4m \times 3m \times 0.30 = 3.6 \text{ cu.m}$

Quantity of plastering (two faces) =  $2 \times L \times H = 2 \times 4m \times 3m = 24 \text{ sq.m}$

cost of brickwork =  $3.6 \times 320.00 = \text{Rs. } 1152.00$

cost of plastering =  $24 \times 2.50 = \text{Rs. } 204.00$

Total cost =  $1152.00 + 204.00 = \text{Rs. } 1356.00$

Ex-2 Prepared a detailed estimate of part of a wall of a building from the given plan and section and general specification (Fig. 2.1 and 2.2)

#### General specification

- (1) Foundation concrete shall be of lime concrete
- (2) Foundation and plinth shall be of 1st class brickwork in lime mortar
- (3) Damp proof course - 2.5mm c.c. 1:1½:3 with water proofing compound
- (4) Superstructure - 1st class brickwork in lime mortar
- (5) Wall finishing. Inside wall 12mm cement plastered 1:6 and white wash 2 coats.

Plan and Section

Fig. 2-1

WALL WITH STANDARD MODULAR BRICKS.





Fig. 2-2

WALL WITH TRADITIONAL BRICKS.





Outside wall 12mm cement plastered 1:6 including 10cm below ground level and finished with 2 coat of colour wash over one coat of white washing.

8017

Item No	Description of item of work	No.	Dimensions			Quantity of contents	Total quantity
			Length	Breadth	Ht. or Depth		
1.	Earthwork in excavation in foundation	1	6.00m	0.80m	0.90m	4.32	4.32 cum
2.	Lime concrete in foundation	1	6.00m	0.80m	0.30m	1.44	1.44 cum
3.	1st class brickwork in lime mortar in foundation and plinth						
	1st footing	1	6.00m	0.60m	0.20m	0.72	
	2nd footing	1	6.00m	0.50m	0.20m	0.60	
	plinth wall up to G.L.	1	6.00m	0.40m	0.20m	0.48	
	plinth wall above G.L.	1	6.00m	0.40m	0.60m	1.44	
						Total: 3.24 cum	
4.	2.5cm Damp proof course (D.P.C) c.c. 1:1½:3	1	6.00m	0.40m	-	2.4	2.4 sq.m
5.	1st class brickwork in lime mortar for superstructure	1	6.00m	0.30m	-	6.3	6.3 sq.m
6.	12mm plaster of cement sand 1:6						
	Inside	1	6.00m	-	3.50m	21.0	
	outside including 10cm below G.L.	1	6.00m	-	4.20m	25.2	
						Total: 46.2 sq.m	
7.	white washing 3 coats (inside)	1	6.00m	-	3.50	21.0	21.0 sq.m
8.	colour washing 2 coats over one coat of white washing (outside above G.L.)	1	6.00m	-	4.10m	24.6	24.6 sq.m

### ABSTRACT OF ESTIMATE COST

Item No.	Description of item of work	Quantity	Unit	Rate Rs.	Per	Amount Rs.
1.	Earthwork in excavation in foundation	4.32	cum	350.00	per cum	1512
2.	Lime concrete in foundation with white lime, surkhi and brick ballast	1.44	cum	220.00	per cum	316.80
3.	1st class brickwork with white lime and surkhi mortar 1:2 in foundation and plinth	3.24	cum	300.00	per cum	972.00
4.	2.5cm thick c.c. 1:1½:3 Damp proof course with water proofing compound	2.4	sq.m	20.00	per sq.m	48.00
5.	1st class brickwork with white lime and surkhi 1:2 mortar in superstructure	6.3	cum	320.00	per cum	2016.00
6.	12mm cement and local sand plaster 1:6	46.2	sq.m	8.50	per sq.m	392.70
7.	white washing 3 coats	21.0	sq.m	0.75	per sq.m	15.75
8.	colour washing 2 coats over one coat of white washing	24.6	sq.m	0.82	per sq.m	20.17



Add for contingencies 3%  
Add for workcharged Establishment 20%

Total = 3796.54  
113.90  
95.93  
Grand Total = 3986.37

## Method of building estimate

### Method 1

Separate or individual wall method:- In this method, measure or find out the external length of walls running in the longitudinal direction generally the long walls out-to-out, and the internal length of walls running in the transverse direction in-to-in i.e. of cross partition wall in-to-in and calculate quantities multiplying the length by the breadth and the height of wall.

Long wall length out-to-out = centre to centre length + half breadth on one outside + centre to centre length + one breadth.

Short wall length in-to-in = centre to centre length - one breadth.

Ex. 3 (a) Fig 2.3, the plan represents the plan of superstructure wall of a single room building of 5m x 4m, and sections represent the cross-sections of the walls with foundation.

Estimate the quantities of -

- (1) Earthwork in excavation in foundation,
- (2) Concrete in foundation.
- (3) Brickwork in foundation and plinth and
- (4) Brickwork in superstructure.



The length of long wall centre to centre =  $5.00 + \frac{1}{2} \times 0.30 + \frac{1}{2} \times 0.30 = 5.30m$ .

The length of short wall centre to centre =  $4.00 + \frac{1}{2} \times 0.30 + \frac{1}{2} \times 0.30 = 4.30m$

Item No.	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory note
1.	Earthwork in excavation in foundation -						
	Long wall	2	6.20	0.90	0.90	10.04	$L = 5.3 + 0.9 = 6.20m$
	Short wall	2	3.40	0.90	0.90	5.51	$L = 4.30 - 0.90 = 3.40m$
					Total =	15.55 cu.m	
2.	Concrete in foundation -						
	Long wall	2	6.20	0.90	0.30	3.35	Length same as excavation quantity
	Short wall	2	3.40	0.90	0.30	1.83	
					Total =	5.18 cu.m	
3.	Brickwork in foundation and plinth -						
	Long wall -						
	1st booting	2	5.90	0.60	0.30	2.13	$L = 5.3 + 0.6 = 5.90m$
	2nd booting	2	5.80	0.50	0.30	1.74	$L = 5.3 + 0.5 = 5.80m$
	Plinth walls	2	5.70	0.40	0.60	2.74	$L = 5.3 + 0.4 = 5.70m$
	Short wall -						
	1st booting	2	3.70	0.60	0.30	1.33	$L = 4.3 - 0.60 = 3.70m$
	2nd booting	2	3.80	0.50	0.30	1.74	$L = 4.30 - 0.50 = 3.80m$
	Plinth walls	2	3.70	0.40	0.60	1.87	$L = 4.3 - 0.40 = 3.90m$
					Total =	10.95 cu.m	



## TWO ROOMED BUILDING



All Walls are of same section  
 Lintels over Doors, Windows and  
 Shelves are 15 cm thick R.B.

Doors D-1.20 m x 2.10 m  
 Windows W-1.00 x 1.50 m  
 Shelves S-1.00 m x 1.50 m

Fig. 2-6

No beam has been shown in the plan as the object of this example is to explain the



Item No.	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory note
A.	Brickwork in Superstructure						
	Long walls	2	5.60	0.30	3.50m	11.76	$L = 5.3 + 0.3 = 5.60m$
	Short walls	2	4.00	0.30	3.50m	8.40	$L = 4.3 - 0.3 = 4.0m$
Total = 20.16 cu.m							

### Ex. 4(a)

Estimate the quantities of the following items of a two roomed building from the given plan and section (Fig. a-c)

- (1) Earthwork in excavation in foundation
- (2) Lime concrete in foundation
- (3) 1st class brickwork in cement mortar 1:6 in foundation and plinth
- (4) 2.5cm c.c. damp proof course and
- (5) 1st class brickwork in lime mortar in superstructure

Ans.

Item No.	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory note
							Long wall, c/c length = $4.6 + 0.30 + 2 \times 0.30 = 10.60m$ Short wall & internal c/c length = $6.42 + 0.30 = 6.30m$
1.	Earthwork in excavation in foundation						
	Long walls	2	11.70	1.10	1.00	25.74	$L = 10.60 + 1.10 = 11.70m$
	Short walls	3	5.20	1.10	1.00	17.16	$L = 6.30 - 1.10 = 5.20m$
						Total: 42.90 cu.m	
2.	Lime concrete in foundation						
	Long walls	2	11.70m	1.10	0.30	7.72	Length same as for excavation
	Short walls	3	5.20m	1.10	0.30	5.15	
						Total: 12.87 cu.m	
3.	1st class brickwork in 1:6 cement mortar in foundation and plinth						
	Long walls -						
	1st footing	2	11.40m	0.80m	0.20m	3.65	$L = 10.60 + 0.80 = 11.40m$
	2nd footing	2	11.30	0.70	0.10	1.58	$L = 10.60 + 0.70 = 11.30m$
	3rd footing	2	11.20	0.60	0.10	1.34	$L = 10.60 + 0.60 = 11.20m$
	4th footing	2	11.10	0.50	0.10	1.11	$L = 10.60 + 0.50 = 11.10m$
	Plinth wall above footing	2	11.00	0.40	0.80	7.04	$L = 10.60 + 0.40 = 11.00m$
	Short walls						
	1st footing	3	5.50	0.80	0.20	2.64	$L = 6.30 - 0.80 = 5.50m$
	2nd footing	3	5.60	0.70	0.10	1.18	$L = 6.30 - 0.70 = 5.60m$
	3rd footing	3	5.70	0.60	0.10	1.03	$L = 6.30 - 0.60 = 5.70m$
	4th footing	3	5.80	0.50	0.10	0.87	$L = 6.30 - 0.50 = 5.80m$
	Plinth wall above footing	3	5.90	0.40	0.80	5.66	$L = 6.30 - 0.40 = 5.90m$
						Total: 26.10 cu.m	
4.	Damp proof course 2.5cm thick c.c.						
	Long walls	2	11.00	0.40	-	8.80	Lengths same as for plinth
	Short wall	3	5.90	0.40	-	7.08	Wall in item 3
						Total: 15.88	
	Deduct door sill	2	1.20	0.40	-	0.96	
						Net Total: 14.92 sq.m	

Item No	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory note.
6	1st class brickwork in lime mortar in super structure.						
	long walls	2	10.90	0.30	4.20	27.47	$L = 10.6 + 0.3 = 10.90 \text{ m}$
	short walls	3	6.00	0.30	4.20	22.68	$L = 6.30 - 0.30 = 6.00 \text{ m}$
						Total = 50.15 cu.m	
	<u>Deduct -</u>						
	Door openings	2	1.20	0.30	2.10	1.51	
	window openings	4	1.50	0.30	1.50	1.80	
	shelves	2	1.00	0.20	1.50	0.60	Back of shelves 10cm thick wall
	Lintel over doors	2	1.50	0.30	0.15	0.14	Beating 15cm
	Lintel over windows	4	1.30	0.30	0.15	0.23	Beating 15cm
	Lintels over shelves	2	1.30	0.30	0.15	0.12	Beating 15cm
						Total of deduction 4.40 cu.m	
						Net Total = 45.75 cu.m	

Ex. 5(a) Estimate the quantities of the following items of a residential building from the given drawing (Fig 2.7):

- (1) Earthwork in excavation in foundation
- (2) Lime concrete in foundation
- (3) First class brickwork 1:6 cement sand mortar in foundation and plinth
- (4) 2.5cm Damp proof course,
- (5) First class brickwork in lime mortar in superstructure.

Ans Drawing and left hand side bed room combined -

$$\text{c. to c. long walls} = 6.00 + 1.00 + 0.30 + 2 \times 0.15 = 10.60 \text{ m}$$

$$\text{c. to c. short walls} = 5.00 + 2 \times 0.15 = 5.30 \text{ m}$$

Bedrooms right side (both combined)

$$\text{c. to c. long walls} = 5.00 + 1.00 + 0.30 + 2 \times 0.15 = 9.60 \text{ m}$$

$$\text{c. to c. short walls} = 4.50 + 2 \times 0.15 = 4.80 \text{ m}$$

Front Verandah

$$\text{Front wall c. to c. length} = 5.00 + 1.00 + 2 \times 0.3 + \frac{0.30}{2} - \frac{0.20}{2} = 9.65 \text{ m}$$



$$\text{side wall c. to c. length} = 2.00 + \frac{0.30}{2} + \frac{0.20}{2} = 2.25 \text{ m}$$

Back verandah including bath room

$$\text{c. to c. long wall (rear wall including bath room)} = 9.65 \text{ m same as front verandah}$$

$$\text{c. to c. length of side wall of bath room} = 2.50 + \frac{0.30}{2} + \frac{0.20}{2} = 2.75 \text{ m}$$





Doors:-  
 $D_1$  - 120 cm x 210 cm (1.20 m x 2.10 m)  
 $D_2$  - 100 cm x 200 cm (1.00 m x 2.00 m)  
 $D_3$  - 75 cm x 180 cm (.75 m x 1.80 m).

Windows:-  
 $W_1$  - 100 cm x 150 cm (1.00 m x 1.50 m)  
 $W_2$  - 200 cm x 150 cm (2.00 m x 1.50 m)  
 $W_3$  - 75 cm x 120 cm (.75 m x 1.20 m)  
 $C.W.$  - 75 cm x 60 cm (.75 m x .60 m).

Shelves:-  
 $S$  - 100 cm x 150 cm (1.00 m x 1.50 m)  
 Lintel Over Doors, Windows Etc.  
 15 cm R.B.

All walls of Drawing Rooms and Bed Rooms have same section

Bath Room walls have similar section.

**Note**—No beam has been shown in the plan.

Fig. 2-7



No.	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
1.	Earthwork in excavation in foundations— Drawing room and left bedroom						
	Long walls	2	11.50	0.90	1.50	20.70	$L = 10.60 + 0.90 = 11.50m$
	Short walls	3	4.40	0.90	1.50	11.28	$L = 5.30 - 0.90 = 4.40m$
	Bedroom right side (both)						
	Long walls	2	9.60	0.90	1.50	17.28	$L = 9.60 - \frac{0.70}{2} + \frac{0.90}{2} = 9.60m$
	Short walls	2	3.90	0.90	1.50	7.02	$L = 4.80 - 0.90 = 3.90m$
	Front Verandah						
	Front long wall	1	9.50	0.60	0.50	2.35	$L = 9.65 - \frac{0.90}{2} + \frac{0.60}{2} = 9.50m$
	Side short wall	1	1.50	0.60	0.50	0.45	$L = 2.25 - \frac{0.90}{2} - \frac{0.60}{2} = 1.50m$
	Back verandah including bath room						
	Long wall (near wall including bath)	1	9.50	0.60	0.50	2.35	$L = 9.65 - \frac{0.90}{2} + \frac{0.60}{2} = 9.50m$
	Short walls (remaining walls of bath)	2	2.00	0.60	0.50	1.20	$L = 2.75 - \frac{0.90}{2} - \frac{0.60}{2} = 2.00m$
						Total: 64.23 cu.m	
2.	Lime concrete in foundation—Drawing and left bedroom						
	Long walls	2	11.50	0.90	0.30	6.21	L same as for earthwork in excavation
	Short walls	3	4.40	0.90	0.30	3.56	
	Bedroom right side (both)						
	Long wall	2	9.60	0.90	0.30	5.18	L same as for earthwork in excavation
	Short walls	2	3.90	0.90	0.30	2.11	
	Front Verandah						
	Front long wall	1	9.70	0.60	0.20	1.16	$L = 9.65 - \frac{0.50}{2} + \frac{0.60}{2} = 9.70m$
	Side short wall	1	1.70	0.60	0.20	0.20	$L = 2.25 - \frac{0.50}{2} - \frac{0.60}{2} = 1.70m$
	Back verandah including bath room						
	Long wall including bath	1	9.70	0.60	0.20	1.16	$L = 9.65 - \frac{0.50}{2} + \frac{0.60}{2} = 9.70m$
	Short wall (remaining walls of bath)	2	2.20	0.60	0.20	0.53	$L = 2.75 - \frac{0.50}{2} - \frac{0.60}{2} = 2.20m$
						Total: 20.11 cu.m	
3.	1st class brickwork in foundations and plinth 1:6 cement mortar Drawing and left bedroom						
	Long walls	2	11.20	0.60	0.20	2.69	$L = 10.60 + 0.60 = 11.20m$
	1st booting	2	11.10	0.50	0.20	2.22	$L = 11.20 - 2 \times 0.05 = 11.10m$
	2nd booting	2	11.50	0.40	0.90	7.92	$L = 11.10 - 0.10 = 11.00m$
	Plinth wall above booting	2					
	Short walls—						
	1st booting	3	4.70	0.60	0.20	1.69	$L = 5.30 - 0.60 = 4.70m$
	2nd booting	3	4.80	0.50	0.20	1.44	$L = 4.70 + 2 \times 0.05 = 4.80m$
	Plinth wall above booting	3	4.90	0.40	0.90	5.29	$L = 4.80 + 0.10 = 4.90m$
	Bedroom right side (both)						
	Long wall—						
	1st booting	2	9.60	0.60	0.20	2.31	$L = 9.60 - \frac{0.6}{2} + \frac{0.6}{2} = 9.60m$
	2nd booting	2	9.60	0.50	0.20	1.92	$L = 9.60 - \frac{0.50}{2} + \frac{0.50}{2} = 9.60m$
	Plinth wall above booting	2	9.60	0.40	0.90	2.91	$L = 9.60 - \frac{0.40}{2} + \frac{0.40}{2} = 9.60m$
	Short wall						
	1st booting	2	4.20	0.60	0.20	1.01	$L = 4.80 - 0.60 = 4.20m$
	2nd booting	2	4.30	0.50	0.20	0.86	$L = 4.20 + 2 \times 0.05 = 4.30m$
	Plinth wall above booting	2	4.40	0.40	0.90	3.17	$L = 4.30 + 0.10 = 4.40m$

Item No.	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
	short wall - 1st footing 2nd footing	2 2	4.20 4.30	0.60 0.50	0.20 0.20	1.01 0.86	$L = 4.20 - 0.60 = 4.20m$ $L = 4.2 + 2 \times 0.05 = 4.30m$
	Plinth wall above footing	2	4.41	0.40	0.90	3.17	$L = 4.30 + 10 = 4.40m$
	Front verandah Front wall Footing	1	9.65	0.40	0.20	0.77	$L = 9.65 - \frac{0.40}{2} + \frac{0.40}{2} = 9.65m$
	Plinth wall above footing	1	9.60	0.30	0.70	2.02	$L = 9.65 - \frac{0.40}{2} + \frac{0.30}{2} = 9.60m$
	Side short wall Footing	1	2.25	0.40	0.20	0.15	$L = 2.25 - \frac{0.4}{2} - \frac{0.4}{2} = 1.85m$
	Plinth wall above footing	1	1.90	0.30	0.70	0.40	$L = 2.25 - \frac{0.4}{2} - \frac{0.3}{2} = 1.90m$
	Back verandah including bath room - Long wall Footing	1	9.65	0.40	0.20	0.77	} Length same as for front verandah long wall
	Plinth wall above footing	1	9.60	0.30	0.70	2.02	
	Short walls (remaining walls of bath) Footing	2	2.35	0.40	0.20	0.38	$L = 2.75 - \frac{0.40}{2} - \frac{0.40}{2} = 2.35m$
	Plinth wall above footing	2	2.40	0.30	0.70	1.01	$L = 2.75 - \frac{0.40}{2} - \frac{0.30}{2} = 2.40m$
					Total	44.95 cu.m	
4.	2.5cm Damp proof course Drawing and left bed room - Long walls Short walls	2 3	11.00 4.90	0.4 0.4	- -	2.80 5.88	L same as plinth wall L same as plinth wall
	Bed room inner side Long walls Short walls	2 2	9.60 4.40	0.4 0.4	- -	7.68 3.52	L same as plinth wall L same as plinth wall
	Verandah pillars Bathroom	4	0.50	0.3	-	0.60	5cm extra on all sides
	Rear wall Side and inter walls	1 2	2.50 2.40	0.30 0.30	- -	0.75 1.44	$L = 2.20 + 2 \times 0.15 = 2.50m$
					Total	28.67 sq.m	
	Deduct - Door sill D <sub>1</sub> Door sill D <sub>2</sub> Door sill D <sub>3</sub>	6 2 1	1.20 1.00 0.75	0.40 0.40 0.30	- - -	2.88 0.80 0.25	
					Total deduction	3.91 sq.m	
					Net total	24.76 sq.m	
5.	1st class brickwork in superstructure in lime mortar Drawing + left bed room	2	10.90	0.30	4.0	26.16	$L = 10.60 + 0.30 = 10.90m$
	Long walls Short walls	3	5.0	0.30	4.0	12.00	$L = 5.3 - 0.3 = 5.0m$
	Bed room right side Long walls Short walls	2 2	9.60 4.50	0.30 0.30	4.0 4.0	23.04 10.80	$L = 9.60 - \frac{0.3}{2} + \frac{0.3}{2} = 9.6m$ $L = 4.80 - 0.30 = 4.50m$
	Front verandah Front wall as solid	1	9.60	0.20	3.05	5.86	$L = 9.65 - \frac{0.3}{2} + \frac{0.2}{2} = 9.60m$
	Side wall as solid	1	2.00	0.20	3.05	1.22	



Item No	Particulars item of work	No	Length in m	Breadth in m	Height in m	Quantity	Explanatory note
	Back verandah including bath —						
	Back long wall as solid	1	9.60	0.20	3.05	5.86	L same as front verandah.
	side and intervals at bath	2	2.50	0.20	3.05	3.05	
					Total	93.99 cum	
	Deduct:						
	Door openings						
	D opening D <sub>1</sub>	6	1.20	0.30	2.10	4.54	
	D opening D <sub>2</sub>	2	1.00	0.30	2.00	1.20	
	D opening D <sub>3</sub>	1	0.75	0.20	1.80	0.27	
	Window openings						
	W opening W <sub>1</sub>	11	1.00	0.30	1.50	4.95	
	W opening W <sub>2</sub>	1	2.00	0.30	1.50	0.90	
	W opening W <sub>3</sub>	2	0.75	0.20	1.20	0.36	
	clerestory window (C.W) openings	18	0.75	0.20	0.60	2.43	
	shelves opening	5	1.00	0.20	1.50	1.50	Back at chelva 10 cm thick wall
	Front verandah openings in between pillars	1	8.40	0.20	2.40	4.83	$L = 9.60 - 3 \times 0.40 = 8.40m$
	Front verandah opening side	1	2.00	0.20	2.40	0.96	
	Back verandah opening	1	6.20	0.20	2.40	3.26	$L = 9.60 - 2.40 - 0.40 = 6.80m$
	Lintels —						
	Over doors						
	D over D <sub>1</sub>	6	1.50	0.30	0.15	0.405	Bearing 15 cm
	D over D <sub>2</sub>	2	1.30	0.30	0.15	0.17	Bearing 15 cm
	D over D <sub>3</sub>	1	0.95	0.20	0.15	0.029	Bearing 10 cm
	Over windows						
	W window W <sub>1</sub>	11	1.30	0.30	0.15	0.644	Bearing 15 cm
	W window W <sub>2</sub>	1	2.30	0.30	0.15	0.103	Bearing 15 cm
	W window W <sub>3</sub>	2	0.95	0.20	0.15	0.057	Bearing 10 cm
	over C.W.	18	0.95	0.20	0.15	0.770	Bearing 10 cm
	over shelves	5	1.30	0.30	0.15	1.293	Bearing 15 cm
	Verandah lintels						
	Front	1	9.75	0.20	0.15	0.292	$L = 9.60 + 0.15 = 9.75m$
	side	1	2.15	0.20	0.15	0.065	$L = 2.00 + 0.15 = 2.15m$
	Back	1	7.50	0.20	0.15	0.225	$L = 9.60 - 2.40 + 0.2 \times 0.15 = 7.50m$
						Total deduction	27.401 cum
						Net total	66.59 cum



## METHOD-II

Centre line method: In this method known as centre line method sum - total length of centre lines of walls, long and short, has to be found out. Find the total length of centre lines of walls, of same type, long and short having same type of foundations and footing and then find the quantities by multiplying the total centre length by the respective breadth and the height.

In this method, the length will remain same for excavation in foundation, for concrete in foundation, for all footings and for superstructure. This method is quick but requires special attention and consideration at the junctions, meeting points of partition or cross walls, etc.

For rectangular, circular polygonal (hexagonal, octagonal, etc.) building having no interior cross walls, this method is quite simple. For buildings having cross or partition walls, for every junction of partition or cross walls with main walls, special consideration shall have to be made to find the correct quantity. For each junction half breadth of item or footing is to be deducted from the total centre lengths. - respective

Ex. 3(b) Estimate by centre line method the quantities of the following items of a single room building Fig 2.3

- Earthwork in excavation in foundation,
- Concrete in foundation,
- Brickwork in foundation and plinth
- Brickwork in superstructure

Ans Total centre length of walls =  $5.20 + 4.30 + 5.30 + 4.30 = 19.20 \text{ m}$ .

S. No.	Particulars of item	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory notes
1.	Earthwork in excavation in foundation	1	19.20	0.90	0.90	15.55 cu.m	Total centre length of all walls = 19.20 m
2.	Concrete in foundation	1	19.20	0.90	0.30	5.18 cu.m	
3.	Brickwork in foundation and plinth						
	1st footing	1	19.20	0.60	0.30	3.46	
	and footing	1	19.20	0.50	0.30	2.88	
	plinth wall	1	19.20	0.40	0.60	4.61	
					Total:	10.95 cu.m	
4.	Brickwork in superstructure	1	19.20	0.30	8.60	20.16 cu.m	Door and window openings, lintels, etc. to be deducted.

Ex. 4(b) Estimate by centre line method the quantities of the following items of a two roomed building Fig 2.6.

- Earthwork in excavation in foundation
- Lime concrete in foundation
- 1st class brickwork in cement mortar in foundation and plinth
- 2.5 cm c.c. damp proof course, and
- 1st class brickwork in lime mortar in superstructure

Ans There are 2 junctions of the inter wall with the main wall.

$$\begin{aligned} \text{Total centre length of wall} &= 2 \times \text{c. to c. of long wall} + 3 \times \text{c. to c. of short wall} \\ &= 2 \times 10.60 + 3 \times 8.30 = 40.10 \text{ m} \end{aligned}$$





## TWO ROOMED BUILDING




Fig. 2-6

Item No.	Particulars of item	No	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation	1	39.00	1.10	1.0	42.90 cu.m	Total centre length = 40.10 m $L = 40.10 - 2 \times \frac{1.0}{2} = 39.00m$
2.	Lime concrete in foundation	1	39.00	1.10	0.30	12.27 cu.m	L same as above
3.	1st class brickwork in 1:6 cement mortar in foundation and plinth—						
	1st footing	1	39.30	0.80	0.20	6.29 cu.m	$L = 40.10 - 2 \times \frac{0.20}{2} = 39.80m$
	2nd footing	1	39.40	0.70	0.10	2.76	$L = 40.10 - 2 \times \frac{0.30}{2} = 39.40m$
	3rd footing	1	39.50	0.60	0.10	2.37	$L = 40.10 - 2 \times \frac{0.60}{2} = 39.50m$
	4th footing	1	39.60	0.50	0.10	1.98	$L = 40.10 - 2 \times \frac{0.50}{2} = 39.60m$
	Plinth wall above footing	1	39.70	0.40	0.50	12.70	$L = 40.10 - 2 \times \frac{0.40}{2} = 39.70m$
					Total	26.10 cu.m.	
4.	Damp proof course 2.5cm c.c. Deduct door sill	1 2	39.70 1.20	0.40 0.40	— —	15.88 0.96	$L = 40.10 - 2 \times \frac{0.40}{2} = 39.70m$
					Net	14.92 cu.m	
5.	1st class brickwork in lime mortar in superstructure Deduct door, window, shaft openings and lintels	1 1	37.80 same as per	0.30	4.20 detail in	50.15 4.40	$L = 40.10 - 2 \times \frac{0.30}{2} = 39.80m$ Deduction to be made as usual
					Net	45.75 cu.m	

Ex 5.6b Estimate by centre line method the quantities of the following items of a residential building. Fig 2.7a

- (1) Earthwork in excavation in foundation
- (2) Lime concrete in foundation
- (3) First class brickwork in 1:6 cement sand mortar in foundation and plinth
- (4) Damp proof course and
- (5) First class brickwork in lime mortar in superstructure.

Ans Total centre length of all 30 cm walls (same type) of main rooms  
 = Total centre length of walls of drawing and 1st side bed room  
 + Total centre length of walls of bed room right side  
 = (2 x c. to c. length of long wall + 3 x c. to c. length of short wall)  
 + (2 x c. to c. length of long wall + 2 x c. to c. length of short wall)  
 = (2 x 10.60 + 3 x 5.30) + (2 x 9.60 + 2 x 4.80)  
 = 37.10 + 28.80 = 65.90 m.


Number of junctions for these walls is 6 marked 'x' in the plan Fig 2.7., all these junctions are with main walls of 30 cm.  
 Total centre length of all 20 cm walls of front verandah, back verandah and bath room  
 = (c. to c. length of front wall + c. to c. length of side wall) + (c. to c. length of back verandah long wall including bath) + 2 x c. to c. length of cross walls of bath room

$$= (9.65 + 2.22) + (9.65 + 2 \times 2.75) = 11.90 + 15.15 = 27.05 m.$$


Item No.	Particulars of item	No	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation — wall of main room (six junctions)	1	63.20	0.90	1.00	56.88	$L = 65.90 - 6 \times \frac{0.90}{2} = 63.20 m$
	walls of verandah including bath (five and one junctions)	1	24.50	0.60	0.50	7.35	$L = 27.05 - 5 \times \frac{0.90}{2} - 1 \times \frac{0.60}{2} = 24.50 m$



# RESIDENTIAL BUILDING



PLAN



CROSS SECTION OF MAIN WALLS

CROSS SECTION AB OF VER. WALL

All walls of Drawing Rooms and Bed Rooms have same section

Bath Room walls have similar section.

**Note**—No beam has been shown in the plan.

Fig. 2-7

Particulars of item	No	L	B	H	Q	Ex. note
1. Lime concrete in bounding walls of main rooms	1	63.21	0.90	0.30	17.06	Length same as earthwork - excavation $L = 27.05 - 6 \times \frac{0.50}{2} - 1 \times \frac{0.60}{2}$ $= 25.50m$ (minus half breadth per junction at the same level)
walls of verandah and bath	1	25.50	0.40	0.20	2.06	
<b>Total</b>					<b>19.12 cum</b>	
2. 1st class brickwork in bounding and plinth in 1:6 cement mortar -						
Walls of main rooms -						
1st footing	1	64.10	0.60	0.20	7.69	$L = 65.90 - 6 \times \frac{0.60}{2} = 64.10m$
2nd footing	1	64.40	0.50	0.20	6.44	$L = 65.90 - 6 \times \frac{0.50}{2} = 64.40m$
Plinth wall above footing	1	64.70	0.40	0.90	23.29	$L = 65.90 - 6 \times \frac{0.40}{2} = 64.70m$
Walls of verandah and bath -						
Footing	1	25.85	0.40	0.20	2.07	$L = 27.05 - 5 \times \frac{0.40}{2} - 1 \times \frac{0.40}{2}$
Plinth wall above footing	1	25.90	0.30	0.70	5.44	$= 25.95m$ $L = 27.05 - 5 \times \frac{0.40}{2} - 1 \times \frac{0.30}{2}$ $= 25.90m$
<b>Total</b>					<b>49.93 cum</b>	
4. 25cm Damp proof course						
Walls of main rooms	1	64.70	0.40	—	25.88	
Verandah pillars	4	0.50	0.30	—	0.60	
Bath rooms (total of 2 walls)	1	7.30	0.30	—	2.19	$L = (4.20 + 2 \times 0.15) + 2 \times (3.75 - \frac{0.4 \times 0.3}{2}) = 7.30m$
<b>Total</b>					<b>28.67 cum</b>	
Deduct door sill					59.15	
same as per detailing					3.91	
<b>Net Total</b>					<b>24.7659 m</b>	

5. 1st class brick-work in super-structure in lime mortar -						
Walls of main rooms	1	65.00	0.30	1.10	78.00	$L = 65.90 - 6 \times \frac{0.30}{2} = 65.10m$
Walls of verandah and bath (as solid)	1	26.20	0.20	5.05	15.98	$L = 27.05 - 5 \times \frac{0.20}{2} - 1 \times \frac{0.20}{2} = 26.20m$
<b>Total</b>					<b>93.98</b>	
Deduct openings and lintels					27.40	
same as deduct.					66.58	
<b>Net Total</b>					<b>66.58 cum</b>	

### Arch calculations :-

The quantities of masonry work in arch is calculated by multiplying the mean length of arch by breadth of wall and by the thickness of arch. In the case of circular the quantity of arch masonry work is equal to the length of arch base  $\pm$  base  $\times$  mean length of arch  $\times$  thickness of arch.


Case I Segmental Arch with span and angle given - Arch of span S subtending an angle Q at the centre

S = span, Q = angle at the centre, r = radius  
 $\pi_m$  = mean radius  
 $l_m$  = mean length of arch, t = thickness of arch,  
 b = breadth of wall

$$\sin \frac{Q}{2} = \frac{S/2}{r}$$

$$\therefore r = \frac{S/2}{\sin \frac{Q}{2}}, \pi_m = r + \frac{t}{2}$$

$$\frac{l_m}{2\pi r_m} = \frac{Q}{360}, \therefore l_m = 2\pi r_m \times \frac{Q}{360}$$



$l_m$  can be found  
 Length of arch  $\times$  breadth of wall  $\times$  thickness of arch



ex.1 An arch of 2.50m span subtends an angle of  $60^\circ$  at the centre. The thickness of arch is 30cm and the breadth of wall is 40cm. Calculate the quantity of arch masonry work.

Ans Radius  $r = \frac{s}{2} \times \frac{1}{\sin 40^\circ} = \frac{2.50}{2} \times \frac{1}{0.6428} = 1.945 \text{ m}$

Mean radius  $r_m = r + \frac{t}{2} = 1.945 + \frac{0.30}{2} = 2.095 \text{ m}$

Mean length of arch  $l_m = 2\pi r_m \times \frac{\theta}{360} = 2 \times \frac{22}{7} \times 2.095 \times \frac{60}{360} = 2.93 \text{ m}$

Quantity of arch masonry =  $l_m \times \text{breadth of wall} \times \text{thickness of arch}$   
 $= 2.93 \times 0.40 \times 0.30 = 0.352 \text{ cum.}$

Case II Segmental Arch of  $60^\circ$  Arches over doors and windows are usually segmental subtending an angle of  $60^\circ$  at the centre.  $60^\circ$  arch forms an equilateral on the span with radius


$l_m$  = mean length of arch,  $r_m$  = mean radius

$s$  = span,  $r$  = radius

$r = s$  and  $r_m = r + \frac{t}{2}$ ,  $\frac{1}{2\pi r_m} = \frac{60^\circ}{360^\circ} = \frac{1}{6}$

$l_m = \frac{1}{6} \times 2\pi r_m = \frac{1}{3}\pi r_m$ ,  $l_m$  can be found

Quantity  $Q = l_m \times \text{breadth of wall} \times \text{thickness of arch}$   
 $= l_m \times b \times t$



ex.2 Calculate the quantity of brickwork in a  $60^\circ$  arch over a door of 1.20m width. The arch is 20cm thick and the thickness of the wall is 30cm.

Ans  $r = 1.20 \text{ m}$ ,  $r_m = r + \frac{t}{2} = (1.20 + \frac{0.20}{2}) = 1.30 \text{ m}$

$l_m = \frac{1}{3}\pi r_m = \frac{1}{3} \times \frac{22}{7} \times 1.30 = 1.36 \text{ m}$

Breadth of wall  $b = 0.30 \text{ m}$ , Thickness of arch  $t = 0.20 \text{ m}$

$\therefore Q = l_m \times b \times t = 1.36 \times 0.30 \times 0.20 = 0.082 \text{ cum.}$

Arch masonry, lintel over openings are all deduction works

plastering and pointing

plastering usually  $12 \text{ mm} (\frac{1}{2})$  thick is calculated in sq.m. For walls the measurement are taken for the whole face of the wall for both sides as solid, and deductions for openings are made in the following manner -

- (i) No deduction is made for ends of beams, posts, rafters, etc.
- (ii) For small opening up to  $0.5 \text{ sq.m}$  ( $5 \text{ sq.ft}$ ) no deduction is made, and at the same time no additions are made for jambs, soffits and ob sills of these openings.
- (iii) For openings exceeding  $0.5 \text{ sq.m}$  ( $5 \text{ sq.ft}$ ) but not exceeding  $3 \text{ sq.m}$  ( $30 \text{ sq.ft}$ ) deduction is made for one face only, and the other face is allowed for jambs, soffits and sills which are not taken into account separately.
- (iv) For openings above  $3 \text{ sq.m}$  ( $30 \text{ sq.ft}$ ) deduction is made for both faces of the opening, and the jambs, soffits and sills are taken into account and added.


As the outer jambs, etc. are much smaller than the inner ones, the deduction is usually made.

For the deduction for each opening the same principle as for masonry work is followed.

plastering of ceiling usually of  $12 \text{ mm} (\frac{1}{2})$  thick is computed in sq.m under a separate head as this work is done with richer mortar. For R.C.C. work



usually no plastering is allowed but both fair finish & then plaster of rich cement mortar may be allowed which should not be taken in the measurements separately. Then rich cement mortar plastering in R.C.C. work may also be taken under a separate item, specially in the ceiling inside room.



$$\text{Inside plaster} = L \times H$$

$$\text{Outside plaster} = L \times H - l \times h$$

Painting: Painting in walls is calculated in sqm for whole surface and deductions similar to plastering are made.

White-washing or Colour-washing or Distemping:

The quantities are computed in sqm and are usually same as for plastering. The inside is usually white washed or distempered and this item will be same as for inside plaster. The outside is colour-washed and the quantities of the colour-washing will be same as for outside plaster. These items need not be calculated separately, but simply written as same as for inside plaster or outside plaster. Number of coats of white washing or colour-washing are taken as one job or work and the rate cover for the number of coats which should not be a multiplying factor. The number of coats should be mentioned in this item. Deductions are dealt in the same manner as for plastering. Other types of surface finishing may also be done and may be taken accordingly.

Painting: Painting or Varnishing of doors and windows are computed in sqm, the dimensions should be taken for outer dimensions of the chowkhat i.e. outer dimensions of doors and windows. The area is measured flat. No separate measurement is taken for the chowkhat, the area is same as the area of wall opening. For iron bars, grills etc. the area of the clear opening inside the chowkhat is taken. For both faces of doors and windows, the simple area as measured above is multiplied by appropriate numbers as below.

- (i) Panelled, braced and braced  
ledged and battened or ledged  
battened and braced  $\rightarrow 2\frac{1}{2}$  times one surface area, for both sides
- (ii) Fully glazed or gauge  $\rightarrow 1$  times one surface area, for both sides
- (iii) Partly panelled and partly glazed  
or gauged  $\rightarrow 2$  times one surface area, for both sides
- (iv) Flush door  $\rightarrow 2$  times one surface area, for both sides
- (v) Venetian  $\rightarrow 3$  times one surface area, for both sides
- (vi) Iron bars, grills in windows  $\rightarrow 1$  times the area of clear opening in  
between chowkhat for over all.

This covers the quantities for painting and varnishing of doors and windows.



is very small, the deduction

usually over a coat or priming. The rates cover for the numbers of coats under one item. The number of coats should be mentioned.

The concealed surface of the chokhat which is in contact with the jamb of the wall is usually painted with two coats of coal tar or solignum and this item is computed separately.

For beams, rafters, purlins, posts, etc. if timber or iron, the area of actual exposed surface is taken for painting.

Corrugated surface is taken as flat and a percentage increase is allowed.

Example Prepare a detailed estimate of a single room building having a front verandah from the given plan, elevation and sectional drawing (Fig. 34). General specifications are as follows.

Foundation and plinth - First class brickwork in 1:6 cement and local sand mortar over lime concrete, 2cm DPC of 1:2 cement mortar mixed with standard water proofing material.

Superstructure - Walls shall be of first class brickwork in lime mortar. Inside and outside walls shall be 12mm plastered with 1:1:6 cement : lime : sand, ceiling shall be 12mm 1:3 cement plastered. Inside shall be white washed three coats and outside shall be colour washed one coat over two coats of white washing.

Door and windows - Door and window chokhats shall be of salwood and shutters shall be 4cm panelled of deodar wood, and painted two coats over one coat of priming.

Sol<sup>n</sup> Centre to centre length of walls -

Long wall c. to c. length =  $4.20 + 0.30 = 4.50\text{m}$


Short wall c. to c. length =  $3.00 + 0.30 = 3.30\text{m}$

Verandah front c. to c. length =  $4.20 + 0.30 = 4.50\text{m}$

Verandah side c. to c. length =  $2.00 + 0.30 = 2.30\text{m}$

Sl. No.	Particulars and details of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation - Room						
	Long walls	2	5.30	0.80	0.65	5.51	$L = 4.50 + 0.80 = 5.30\text{m}$
	Short walls	2	2.50	0.80	0.65	2.60	$L = 3.30 - 0.80 = 2.50\text{m}$
	Verandah - pillars	3	0.70	0.70	0.65	0.96	
	Plinth dwarf wall front (sum total length)	1	3.10	0.40	0.25	0.31	$L = 4.50 - 2 \times 0.70 = 3.10\text{m}$
	Plinth dwarf wall side	2	1.55	0.40	0.25	0.31	$L = 2.30 - \frac{0.80}{2} - \frac{0.70}{2} = 1.55\text{m}$
	step	1	2.10	0.65	0.10	0.14	
						Total =	9.83 cu.m.
2.	Earthwork in filling in plinth -						
	Room	1	4.10	2.90	0.375	4.46	
	Verandah	1	4.50	2.10	0.375	3.54	$L = 4.90 - 0.40 = 4.50\text{m}$ $B = 2.35 - 0.20 - 0.05 = 2.10\text{m}$
						Total =	8.00 cu.m.
	Deduct -						
	projection of central pillar	1	0.40	0.20	0.375	0.03	
	projection of side pillar	2	0.20	0.20	0.375	0.03	
						Total =	0.06

These deductions may be neglected being small





No.	Particulars of items and details of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
3.	Lime concrete in foundation Room -						
	Long walls	2	5.30	0.80	0.30	2.54	
	short walls	2	2.50	0.80	0.30	1.20	
	Verandah pillars	3	0.70	0.70	0.30	0.44	
	Dwarf wall front (sum total length)	1	3.70	0.40	0.10	0.15	$L = 4.50 - 2 \times 0.40 = 3.70 \text{ m}$
	Dwarf wall sides	2	1.85	0.40	0.10	0.15	$L = 2.30 - \frac{0.50}{2} - \frac{0.40}{2} = 1.85 \text{ m}$
	step	1	2.10	0.65	0.06	0.08	
						Total = 4.56 cu.m.	
4.	1st class brickwork in foundation and plinth in lime mortar - Room -						
	Long walls						
	1st footing	2	5.10	0.60	0.10	0.61	$L = 4.50 + 0.60 = 5.10 \text{ m}$
	2nd footing	2	5.00	0.50	0.10	0.50	$L = 4.50 + 0.50 = 5.00 \text{ m}$
	plinth wall above footing	2	4.90	0.40	0.60	2.35	$L = 4.50 + 0.40 = 4.90 \text{ m}$
	short walls						
	1st footing	2	2.70	0.60	0.10	0.32	$L = 3.30 - 0.60 = 2.70 \text{ m}$
	2nd footing	2	2.80	0.50	0.10	0.28	$L = 3.30 - 0.50 = 2.80 \text{ m}$
	plinth wall	2	2.90	0.40	0.60	1.37	$L = 3.30 - 0.40 = 2.90 \text{ m}$
	Verandah -						
	Pillar footing	3	0.50	0.50	0.10	0.075	
	Pillar plinth	3	0.40	0.40	0.70	0.336	
	Dwarf wall front (sum total length)	1	3.70	0.20	0.60	0.44	$L = 4.50 - 2 \times 0.40 = 3.70 \text{ m}$
	Dwarf wall sides	2	1.90	0.20	0.60	0.46	$L = 2.30 - 0.4 = 1.90 \text{ m}$
	step:						
	1st step	1	2.00	0.60	0.19	0.23	
	2nd step	1	1.40	0.30	0.15	0.06	
						Total = 7.05 cu.m.	
5.	2cm D.P.C. of 1:2 cement mortar with water-proofing materials -						
	Long walls	2	4.90	0.40	-	3.92	Length, breadth same as plinth wall
	short walls	2	2.90	0.40	-	2.32	
	Verandah -						
	pillars	3	0.40	0.40	-	0.48	
	Deduct door sills	2	1.00	0.40	-	0.60	
						Total = 5.92 sq.m.	
6.	I-class brickwork in super-structure in lime mortar Room -						
	Long walls	2	4.80	0.30	3.50	10.08	$L = 4.50 + 0.30 = 4.80 \text{ m}$
	short walls	2	3.00	0.30	3.50	6.30	$L = 3.30 - 0.30 = 3.00 \text{ m}$
	Verandah -						
	pillars	3	0.30	0.30	2.20	0.59	
	front above lintel	1	4.80	0.30	0.40	0.57	
	sides above lintel	2	2.00	0.30	0.40	0.48	
	parapet long walls	2	4.80	0.20	0.375	0.72	
	parapet short walls	2	3.20	0.20	0.375	0.48	
						Total = 19.22	
	Deduct:						
	Door openings	2	1.00	0.30	2.00	1.20	
	window openings	2	1.00	0.30	1.40	1.26	

No.	Particulars of item and detail of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
	ventilators	2	0.60	0.30	0.30	0.11	
	Lintel over doors	2	1.20	0.30	0.10	0.07 (a)	15cm bearing
	Lintel over windows	3	1.20	0.30	0.10	0.11 (a)	
	Lintel over shelves	1	1.20	0.30	0.10	0.07 (a)	Total of (a) = 0.29 cum
	Lintel over ventilation	1	0.80	0.30	0.10	0.02 (a)	
			Total of b deducting = 3.15 cum				
			net total =			16.07 cum	
7.	Reinforced Brick work in 1:3 cement mortar excluding steel and its bending but including centering and shuttering and binding steel						
	Roof of room	1	5.00	3.80	0.15	2.850	
	Roof of verandah	1	5.00	2.55	0.10	1.275	15cm bearing
	Lintel verandah front	1	4.80	0.30	0.20	0.288	out to out
	Lintel verandah sides	2	2.15	0.30	0.20	0.258	15cm bearing
	Lintel over doors, windows etc		same as for items marked (a) in item (a)			0.240	
			Total			4.911 cum	
8.	7.5cm lime concrete in roof terracing complete with surface finishing -						
	Roof of room	1	4.40	3.20	-	14.08	
	Roof of verandah	1	5.00	2.40	-	12.00	
			Total =			26.08 cum	
9.	Solwood work in chawkhat - Doors (including 4cm inserts into bloom) windows						
		2	5.08	0.10	0.08	0.081	{ 2 vent - 2.04m each 2 Hor. - 1.00m each
		3	4.80	0.10	0.08	0.115	{ 2 vent - 1.40m each 2 Hor. - 1.00m each
			Total =			0.196 cum	
10.	4cm thick Panelled shutter of Deodar wood Doors windows						
	Doors	2	0.87	1.935	-	3.367	15cm rebate
	Windows	3	0.87	1.27	-	3.315	
			Total			6.682 sq.m.	
11.	Iron fittings including screws and tying bars and windows		same as for item (10)			6.68 sq.m.	
12.	Precast R.C.C. slab shelf complete work including steel reinforcement and formwork						
		3	1.08	0.20	0.05	0.032 cum	4cm bearing
13.	R.C.C. jaliwork 4cm thick in ventilators complete work including steel reinforcement and formwork						
		2	0.60	0.30	-	0.36 sq.m.	
14.	Mild steel in Reinforcement bars including bending in R.B. work (at 7.1.11.11.11.11) Hold fasts in doors and windows		$\frac{1.91 \times 7}{100} \times 72.5 = 2.6989$			Density of mild steel = 78.5 g/cu. cm	
		24 @ 1 kg each =	24 = 0.249			6 nos in each door and 4 nos in each window (Hold fasts) to be taken under separate item	
			Total =			2.9389	



Item No.	Particulars of items and Detail of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
15.	25mm c.c. 1:2:4 floor over and including 75mm lime concrete Room Verandah Deduct - central pillars side pillars	1 1  1 2	4.20 4.50  0.30 0.15	3.00 2.15  0.15 0.15	- -  - -	12.60 9.62  0.45 0.15	Total = 22.28  L = out to out - 2 dwarf walls = (4.2 + 2 x 0.30 + 2 x 0.05) - (2 x 0.20) = 4.50m B = (2.0 + 0.30 + 0.05) = 0.20 x 2.15m
16.	25mm c.c. 1:2:4 floor (without lime concrete) - Door sills sills of verandah opening - Front - in between pillars sides	2 1 2	1.00 3.90 2.00	0.30 0.20 0.20	- - -	0.60 0.78 0.80	Total = 2.18 sq.m  L = 4.20 - 3 x 0.30 = 3.90m
17.	12mm plastering in ceiling with 1:3 cement and coarse sand mortar - Room Verandah	1 1	4.20 4.20	3.00 2.00	- -	12.60 8.40	Total = 21.00 sq.m
18.	12mm plastering in walls with 1:1.5:6 cement lime and local sand mortar Inside - Room Long walls short walls Jamb, sill and sabb of shelf Verandah - Wall Pillar inner face Verandah above pillar (inner face) front - DO - sides sabb of verandah lintel front sabb of verandah/lintel sides vertical faces of inner wall below lintel	2 2 1 1 7 1/2 1 2 2	4.20 3.00 5.40 4.20 0.30 4.20 2.00 3.90 2.00 2.00	- - 0.20 - - - 0.30 - 0.30 0.30	3.50 3.50 - 2.80 2.20 0.60 0.60 - - 2.20	24.90 21.00 - 11.76 4.62 2.50 2.40 1.17 1.20 1.32	L = 1.00 x 2 + 1.70 x 2 = 5.40m  3 faces of central pillar and 2 faces of each end pillar  L = 4.20 - 3 x 0.30 = 3.90m
	Deduct door openings outside	2	1.00	-	-	2.00 7.00	one surface to each Total of inside plastering
	Room - Back wall side wall Plinth including 10cm below G.L. and 5cm offset back - DO - sides Front wall above verandah roof Roof projection front and back - DO - sides Verandah pillar outer faces Verandah above pillars (outer face) front - DO - sides	1 2 1 2 1 2 2 5 1	4.80 3.60 4.90 3.65 4.80 5.00 3.60 0.30 4.20	- - - - - - - - -	3.50 3.50 0.60 0.60 0.525 0.25 0.25 2.20 0.60	16.80 25.20 2.94 4.38 2.52 2.50 1.80 3.30 59.44	H <sub>1</sub> = 0.45 + 0.05 + 0.10 = 0.60m H <sub>2</sub> = 3.50 - 2.975 = 0.525m H <sub>3</sub> = 0.15 + 0.10 = 0.25m one face of central pillar and two faces each of end pillars.

No.	Particulars of item and details of work	Sl. No.	Length (m)	Breadth (m)	Height (m)	Quantity	Explanatory Notes
	Vernandah plinth wall front - De - side	1	4.90	-	0.55	2.70	step to be deducted Total centre length $= 2 \times 4.60 + 2 \times 3.10$ $= 16.00 \text{ m}$ $Ht = 0.30 + 0.30 + 0.375$ $= 0.975 \text{ m}$
	Tanapet walls (all four walls)	2	2.35	-	0.05	2.59	
		3	16.00	-	0.975	14.60	
					Total:-	24.37	
	Deduct:-						
	Window opening ventilator step	3	1.00	-	1.40	4.20	one base of each No deductions
		1	2.00	-	0.55	1.10	
					Total	5.30	
					Net Total =	79.07 sq.m	Total of outside plastering

19. 20mm cement plaster 1:3 in steps finished with neat cement —

1st step  
Tread  
Rise  
2nd step -  
Tread  
Rise  
Plinth wall

1	2.60	0.30	-	0.78
1	3.70	-	0.15	0.48
1	1.40	0.30	-	0.42
1	2.60	-	0.15	0.30
1	1.40	-	0.15	0.21
2	0.30	-	0.30	0.12

Total:- 2.37 sq.m

20. White washing 3 coats inside wall ceiling

	Same as inside plaster in item (19)	-	72.47
	Same as ceiling plaster in item (17)	-	21.00
	Total:-	93.47	sq.m

21. Colours washing one coats over two coats of white washing

	Same as outside plaster in item (19)	79.07	
1	Deduction portion below G.L.	19.80	- 0.10 1.98
	Total:-	77.09	sq.m

L = outer perimeter minus step  
 $= (4.90 \times 2 + 6.00 \times 2) - 2.00$   
 $= 19.80 \text{ m}$

22. painting of doors and window two coats over one coats of priming -  
Doors  
Windows

2x24 x 1.7	-	2.00	9.00
3x24 x 1.00	-	1.40	9.45
		Total:	18.45 Sq.m

1/2 ton one face  
1/3 ton one face

23. Coal tarring two coats on back of chowkhat  
Doors  
Windows

2	5.08	0.10	-	1.02
3	4.80	0.10	-	1.44
				2.46

Length same as chowkhat in item 9



# Centreline method single room building with front verandah.

Estimate the following items


- Earthwork in excavation
- Lime concrete in foundation
- First class brickwork in foundation and plinth
- Damp proof course
- First class brickwork in superstructure

Total length of centre line of walls of room =  $4.50 \times 2 + 3.30 \times 2 = 15.60 \text{ m}$

Total length of centre line of walls of verandah =  $4.5 \times 2.30 \times 2 = 9.10 \text{ m}$

Total length of centre line of walls of parapet =  $4.60 \times 2 + 3.40 \times 2 = 16.00 \text{ m}$

Item No.	Particulars of item and details of works	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory note
1.	Earthwork in excavation in foundation - Room verandah pillars plinth dwarf wall step	1 3 1 1	15.60 0.70 6.20 2.10	0.80 0.70 0.40 0.65	0.65 0.65 0.25 0.10	8.11 0.96 0.62 0.14	No junctions $L = 9.10 - 2 \text{ pillars} - \frac{1}{2} \times 2 \text{ junction}$ with main wall $= 9.10 - 3 \times 0.70 - \frac{1}{2} \times 2 \times 0.3 = 6.20$
2.	Lime concrete in foundation Room verandah pillars plinth dwarf wall step	1 3 1 1	15.60 0.70 7.50 2.10	0.80 0.70 0.40 0.65	0.30 0.30 0.10 0.06	3.74 0.44 0.30 0.08	Total = 4.56 cum. $L = 9.10 - 3 \times 0.40 - \frac{1}{2} \times 2 \times 0.4 = 7.50 \text{ m}$
3.	I-class brick in foundation and plinth - Room 1st footing 2nd footing plinth wall verandah pillars 1st footing plinth wall verandah dwarf wall step - 1st step 2nd step	1 1 1 1 3 3 1 1 1	15.60 15.60 15.60 0.50 0.40 7.50 2.00 1.40	0.60 0.50 0.40 0.50 0.40 0.20 0.60 0.30	0.10 0.10 0.60 0.10 0.70 0.60 0.19 0.15	0.93 0.78 3.74 0.075 0.335 0.90 0.23 0.06	Total = 7.05 cum.
4.	2cm D.P.C. Room verandah pillars Deduction door cills	1 3 2	15.60 0.40 1.00	0.40 0.40 0.4	— — —	6.24 0.48 —	Total = 6.72 0.80
5.	I-class brickwork in superstructure in lime mortar - Room verandah (as solid) parapet Deduct - verandah opening sides verandah opening front verandah lintel front verandah lintel sides Deduction of doors, windows etc.	1 1 1 1 1 2 2 2 2	15.60 8.20 16.00 3.70 2.00 4.20 2.15	0.30 0.20 0.20 0.20 0.20 0.30 0.30 0.30	3.50 2.80 0.375 2.20 2.20 0.20 0.20	16.38 7.39 1.20 2.57 2.64 0.29 0.25	Total = 29.97 cum. $L = 9.10 - \frac{1}{2} \times 0.30 = 8.80 \text{ m}$ $L = 4.20 - 3 \times 0.30 = 3.90 \text{ m}$
							5.15





# ESTIMATING AND COSTING

## TWO-ROOM BUILDING WITH FRONT VERANDAH





Fig. 3-5

# CROSS-SECTION OF TWO-ROOMED BUILDING



SEC<sup>NL</sup> ELEVATION ON CEFG

Fig. 3-6



Prepare a detailed estimate of a two roomed building with front verandah from the given drawings plan, elevations, etc (fig-3.5 and 3.6). Calculate also the plinth area rate. The General Specifications are as follows

Foundation and plinth - 1st class brickwork in 1:6 cement mortar over lime concrete

Damp proof course (D.P.C) - 2cm thick cement mortar 1:2 with 1.00 kg of composed pozzol of cement

Superstructure - 1st class brickwork in lime mortar. All lintel shall be R.B.

Roof - Lime concrete terracing over R.C.C. slab with an insulation layer of sand and clays in between.

Flooring - 2.5cm thick C.C. 1:2:4 over 8cm thick lime concrete, over well rammed earth, surface neat cement finished. Sills of doors and verandah openings shall have only 2.5cm C.C. floor.

Plastering and finishing - Inside and outside walls 12mm thick plastered with 1:1:6 cement:lime:sand mortar. Steps 20mm thick cement plastered 1:3 and neat cement finished. R.C.C. work in sun-shade and chhajjas should be fair and smooth finished without any extra payment. Inside white washed 3 coats and outside colour washed 2 coats over 1 coat of white washing.

Door and windows - Chowkhat (frame) shall be of well seasoned salwood. shutters shall be 4cm thick panelled of Indian teak wood. C.S window shutters shall be 4cm thick glazed. Door and windows shall be painted 2 coats over 1 coat of priming. Back of chowkhat shall be painted with 2 coats of solignum.

Miscellaneous item - Windows shall be provided with 16mm dia mild steel bar. Necessary iron hold fasts shall be provided in door and windows. 4 nos. rain water spouts of 10cm dia. C.I. pipe 1m long each shall be provided

Centre to centre lengths

Room Long walls =  $3.50 + 4.00 + 0.30 + (2 \times \frac{0.30}{2}) = 8.10$  m combined total length

Room short walls =  $4.00 + (2 \times \frac{0.30}{2}) = 4.30$  m

Verandah front - Extreme outer length at plinth -  $(2 \times \frac{0.30}{2})$   
 $= \{ 3.50 + 4.00 + (3 \times 0.30) + (2 \times 0.05) \} - 0.30 = 8.20$  m

Verandah sides =  $2.50 + \frac{0.30}{2} + \frac{0.30}{2} = 2.75$  m.

Item No.	Particulars of item and details	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation - Room Long walls short walls Verandah front Verandah sides step	2 3 1 2 1	9.00 3.40 8.90 1.95 2.90	0.9 0.9 0.7 0.7 1.00	0.9 0.9 0.9 0.9 0.15	14.58 8.26 5.61 2.46 0.14	$L = 8.10 + 0.90 = 9.00$ m. $L = 4.30 - 0.90 = 3.40$ m $L = 8.20 + 0.70 = 8.90$ m. $L = 2.75 - \frac{0.9}{2} - \frac{0.7}{2} = 1.95$ m $L = 2.70 + (2 \times 0.10) = 2.90$ m Total = 31.35 cu.m
2.	Earthwork in filling in plinth - Room (i) Room (ii) Verandah	1 1 1	3.90 3.90 7.90	3.40 3.40 2.40	0.54 0.54 0.54	7.16 2.22 10.23	$L = 4.0 - 0.10 = 3.90$ m $B = 3.50 - 0.10 = 3.40$ m $H = 60 + 2.8 = 54$ cm = 0.54 m $L = 8.20 - 0.30 = 7.90$ m $B = 2.75 - \frac{0.40}{2} - \frac{0.30}{2} = 2.40$ m Total = 25.61 cu.m
3.	Lime concrete in foundation Rooms Long walls short walls	2 3	9.0 3.4	0.9 0.9	0.3 0.3	4.86 2.75	may be taken $\frac{1}{3}$ of excavation



# Estimate of a 2 room building with front verandah

Prepare a detailed estimate of a two roomed building with front verandah from the given drawings: plan, elevation, etc (Fig. 3-5 and 3-6). Calculate also the plinth area. The general specifications are as follows:

Foundation and plinth - 1st class brickwork in 1:6 cement mortar over lime concrete damp proof course (D.P.C.) - 2cm thick cement mortar 1:2 with 1.00 kg of composed per bag of cement

Superstructure - 1st class brickwork in lime mortar. All lintel shall be R.B.

Roof - Lime concrete terracing over R.C.C. slab with an insulation layer of sand and clays in between.

Flooring - 2.5cm thick C.C. 1:2:4 over 8cm thick lime concrete, over well rammed earth, surface neat cement finished. Sills of doors and verandah openings shall have only 2.5cm C.C. floor.

Plastering and finishing - Inside and outside walls 12mm thick plastered with 1:1:6 cement:lime:sand mortar. Steps 20mm thick cement plastered 1:3 and neat cement finished. R.C.C. work in sun-shade and chhajja should be fair and smooth finished without any extra payment. Inside white washed 3 coats and outside colour washed 2 coats over 1 coat of white washing.

Door and windows - Chowkhat (frame) shall be of well seasoned sal wood. Shutter shall be 4cm thick panelled of Indian teak wood. C.S. window shutter shall be 4cm thick glazed. Door and window shall be painted 2 coats over 1 coat of priming. Back of chowkhat shall be painted with 2 coats of solignum.

Miscellaneous items - Windows shall be provided with 16mm dia mild steel bar. Necessity iron hold fasts shall be provided in door and window. 4 nos. running water spouts of 10cm dia. C.T. pipe 1cm long each shall be provided.

## Centre to centre lengths

$$\text{Room Long walls} = 3.50 + 4.00 + 0.30 + (2 \times \frac{0.30}{2}) = 8.10 \text{ m combined total length}$$

$$\text{Room short walls} = 4.00 + (2 \times \frac{0.30}{2}) = 4.30 \text{ m}$$

$$\text{Verandah front - Extreme outer length at plinth} - (2 \times \frac{0.30}{2}) \\ = \{ 3.50 + 4.00 + (3 \times 0.30) + (2 \times 0.05) \} - 0.30 = 8.20 \text{ m}$$

$$\text{Verandah sides} = 2.50 + \frac{0.30}{2} + \frac{0.30}{2} = 2.75 \text{ m}$$

Item No.	Particulars of item and details of works	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation — Room Long walls short walls Verandah front Verandah sides step	2 3 1 2 1	9.00 3.40 8.90 1.95 2.90	0.9 0.9 0.7 0.7 1.00	0.9 0.9 0.9 0.9 0.15	14.58 8.26 5.61 2.46 0.14	$L = 8.10 + 0.90 = 9.00 \text{ m}$ $L = 4.30 - 0.90 = 3.40 \text{ m}$ $L = 8.20 + 0.70 = 8.90 \text{ m}$ $L = 2.75 - \frac{0.9}{2} - \frac{0.7}{2} = 1.95 \text{ m}$ $L = 2.70 + (2 \times 0.10) = 2.90 \text{ m}$ Total = 31.35 cu.m
2.	Earthwork in filling in plinth — Room (i) Room (ii) Verandah	1 1 1	3.90 3.90 7.90	3.40 3.40 2.40	0.54 0.54 0.54	7.16 8.22 10.28	$L = 4.0 - 0.10 = 3.90 \text{ m}$ $B = 3.50 - 0.10 = 3.40 \text{ m}$ $H = 60 + 2.8 = 54 \text{ cm} = 0.54 \text{ m}$ $L = 8.20 - 0.30 = 7.90 \text{ m}$ $B = 2.75 - \frac{0.40}{2} - \frac{0.30}{2} = 2.40 \text{ m}$ Total = 25.61 cu.m
3.	Lime concrete in foundation Rooms — Long walls short walls	2 —	9.0 2.11	0.9 0.9	0.3 0.3	4.86 2.75	may be taken 1/3 of excavation



Item No.	Particulars of item of work.	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
	Verandah — Front (long) side (short)	1 2	8.40 2.50	0.20 0.20	0.40 0.40	0.67 0.40	$H = 27 + 10 + 3 = 40 \text{ cm} = 0.4 \text{ m}$
						Total = 29.96 cum	
	Deduct : Door openings window openings C.S. window openings shelves R.B. lintel over Doors windows C.S. window shelves	2 10 12 2 2 10 12 2	1.20 1.00 1.00 1.00 1.40 1.20 1.20 1.20	0.30 0.30 0.30 0.20 0.30 0.30 0.30 0.30	2.10 1.50 0.50 1.50 0.10 0.10 0.10 0.10	1.51 4.50 1.20 0.60 0.084 0.360 0.432 0.072	10cm bearing Total (a) = 0.948 cum
						Total = 9.36	
						Net Total = 30.10 cum	
7.	R.B. lintel over excluding steel and its bending but including centering and shutter and binding steel over doors, window and shelves over Ver. pillars front sides	5. 1 2	Same as bottom work 8.40 2.80	0.20 0.20	0.30 0.30	0.504 0.336	all to all Inside bearing 30cm
						Total = 1.788 cum	
8.	R.C.C. work in verandah columns excluding steel and its bending but including form work and binding steel complete there finished	$4 \times \frac{21}{24} (0.15)^2 \times 7$	2.70	0.17	0.17	0.19	30cm insertion into the plinth wall below blwn.
9.	R.C.C. work excluding steel and its bending but including centering and shuttering and binding steel, built finished — Roof slabs rooms Roof slab verandah Chhajja projections ver. front ver. sides Sun shed and breakers in windows — Top Bottom sides shelves slabs	1 1 1 2 4 4 4 2 2 3	8.64 8.40 9.30 2.70 2.50 2.50 1.50 1.10	0.24 2.80 0.45 0.45 0.45 0.15 0.50 0.20	0.12 0.10 0.06 0.06 0.05 0.05 0.15 0.05	5.018 2.352 0.25 0.144 0.225 0.075 0.195 0.066	12cm projections 10cm inner bearing, excluding chajja. Average thickness 5cm insertion into wall. 5cm insertion and average breadth
						Total = 8.328 cum	
10.	Mild steel bars including bending in reinforcement @ 1% of R.B. and R.C.C. work.		$10.31 \times \frac{1}{10} \times 78.5$			8.109	1% of total of item 9, 809

Item No.	Particulars of item of work.	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
11.	10cm lime concrete in roof terracing complete with surface finishing - Rooms Verandah	1 1	8.00 8.00	4.20 2.50	- -	33.60 20.00	clear roof area in between parapet clear roof area in between parapet
						Total: 53.60 sq.m	
12.	3cm thick insulation layer of sand and clay Rooms Verandah	1 1	8.00 8.00	4.20 2.50	- -	33.60 20.00	clear roof area clear roof area
						Total: 53.60 sq.m	
13.	Salwood work in chowkiat wrought braced and beaded Door (3cm insertion into blank) Windows c.s. window	2 10 12	5.46 5.00 3.00	0.12 0.10 0.08	0.08 0.08 2.08	0.105 0.400 0.230	2 vert. + 213.75 each 1 Hor. - 1.20m each 2 vert. - 1.50m each 2 Hor. - 1.00m each 2 vert. - 0.50m each 2 Hor. - 1.00m each
						Total: 0.735 sq.m	
14.	4cm thick Indian teak wood panelled door and window shutters including battings. Doors windows	2 10	1.07 0.87	- -	2.035 1.37	4.855 11.919	Rebate 1.5 (10)
						Total: 16.274 sq.m	
15.	4cm thick Indian teak wood glazed shutters including battings c.s. windows	12	0.87	-	0.37	8.863 sq.m	
16.	Iron work (mild steel) in hold backs and windows greathings. Hold back in doors Hold back in window Hold back in c.s. window	2x6 10x4 12x2	- - -	- - -	- - -	12 nos. 40 nos. 24 nos.	6 nos. per door 4 nos. per window 2 nos. per c.s. window
						Total 76 nos. @ 1 kg each 76 kg	
	Window bars 16mm dia. Q.I. SS 1kg/m - windows c.s. windows	10x8 12x2	1.50 1.50	- -	- -	120 24	Ver. bars at 10cm centres approx. Two horizontal bars.
17.	80mm thick cement plaster 1:3 to slop finished cement rendered - 1st step riser 2nd step riser 3rd step riser 1st step tread 2nd step tread 3rd step tread Plinth wall above 1st step 2nd step 3rd step	1 1 1 1 1 1 1 2 2 1	4.50 3.30 2.10 3.90 2.70 1.50 0.30 0.30 1.50	- - - - - - - - - -	0.15 0.15 0.15 0.30 0.30 0.30 0.45 0.20 0.15	0.15 0.15 0.15 0.30 0.30 0.30 0.27 0.18 0.21	Front and sides Front and sides Front and sides Front and sides Front and sides Front and sides Sides Sides Sides
						Total: 1.39 sq.m	



## Centre line method - 2 room building

Total length of centre line of all walls of room =  $(2 \times 8.10) + (2 \times 4.20) = 24.60\text{m}$

Number of junctions in 2 of similar walls

Total length of all centre lines of all walls of verandah =  $8.20 + 2 \times 2.75 = 13.70\text{m}$

Number of junctions is 2 of dissimilar walls at the same level

	Itm.	L. m	B. m	Thick. m	Quanti.	Explanatory Note.
1) Earthwork in excavation in foundation						
Rooms		28.20	0.90	0.90	22.24	$L = 24.10 - 2 \times \frac{0.90}{2} = 22.20\text{m}$
Verandah		12.20	0.70	0.70	8.06	$L = 13.70 - 2 \times \frac{0.70}{2} = 12.30\text{m}$
Total = 30.90 cum.						

2) Lime concrete in foundation						
Rooms	1	28.20	0.90	0.30	7.61	} length same as above.
Verandah	1	12.20	0.70	0.30	2.69	
Total = 10.30 cum.						

3) 1-class brickwork in foundation and plinth in 1:6 cement mortar -						
Rooms -						
1st footing	1	28.40	0.70	0.20	3.98	$L = 24.10 - 2 \times \frac{0.70}{2} = 22.40\text{m}$
2nd footing	1	28.50	0.60	0.10	1.71	$L = 24.10 - 0.60 = 23.50\text{m}$
3rd footing	1	28.60	0.50	0.10	1.43	$L = 24.10 - 0.50 = 23.60\text{m}$
plinth wall above footing	1	28.70	0.40	0.20	9.12	$L = 24.10 - 0.40 = 23.70\text{m}$
Verandah -						
1st footing	1	13.00	0.50	0.20	1.30	$L = 13.70 - 2 \times \frac{0.50}{2} = 13.00\text{m}$
2nd footing	1	13.10	0.40	0.10	0.52	$L = 13.70 - 0.60 = 13.10\text{m}$
plinth wall above footing	1	13.20	0.30	0.10	0.40	$L = 13.70 - 0.50 = 13.20\text{m}$
plinth wall above footing	1	13.30	0.30	0.20	3.19	$L = 13.70 - 0.40 = 13.30\text{m}$
Total = 21.71 cum.						

5) 2cm Damp proof course -						
Rooms	1	28.70	0.40	-	11.48	length same as plinth wall
Deduct door sills	2	1.20	0.40	-	0.96	
Total = 10.52 sq.m						

6) 1-class brickwork in super-structure in lime mortar -						
Rooms	1	28.80	0.30	0.20	34.56	$L = 24.10 - 0.30 = 23.80\text{m}$
Verandah above lintel	1	13.40	0.20	0.30	0.80	$L = 13.70 - 0.30 = 13.40\text{m}$
Parapet over rooms	1	25.20	0.20	0.60	3.02	Total centre line length = $2 \times 2.20 + 2 \times 4.40 = 11.00\text{m}$
Parapet over verandah	1	13.40	0.20	0.40	1.07	Total length = $1 \times 8.40 + 2 \times 2.50 = 13.40\text{m}$
Total = 39.45						

Deduct openings, lintel, etc. as usual - 9.36 Details same as

Net Total = 30.09 cum.

\* \* \* \* \*

Estimate of a 2 roomed building with front & back verandah

Q.6 The plan and sectional elevation of a building are given in Fig 3.1. Estimate the quantities of the following items of work of the building.  
 (1) Earthwork in excavation in foundation, (2) Lime concrete in foundation, (3) 1st class brickwork in 1:6 cement mortar in foundation and plinth, (4) Damp proof course, (5) 1st class brickwork in 1:6 cement mortar in superstructure including parapet, (6) R.C.C. work in roof slab, lintels, sunshade etc.  
 (7) steel reinforcement bars in R.C.C. work at 1%.

Ans. Centre to centre length of two adjoining rooms  $(3.6 \times 4.5\text{m room and } 3.6 \times 4.2\text{m room})$  combined.

Long walls - 9.80m, short walls - 3.93m

square room -  $(3.6 \times 3.6\text{m room})$



Long walls - 3.90m, short walls - 3.90m

Verandah Centre to centre of 30cm wall and 30cm sq pillar -

front verandah (1.80m wide)

Long wall (front) - 3.90m, short wall (side) - 2.50m

# THREE ROOMED BUILDING WITH FRONT AND BACK VERANDAH





Sl. No.	Particulars of item and details of work	No.	Length m	Breadth m	Height m	Quantity	Explanatory Note
1.	Earthwork in excavation in bounds.						
	Adjoining rooms combined -						
	Long wall	2	10.10	0.90	0.90	16.36	$L = 9.20 + 0.90 = 10.10m$
	short wall	2	3.00	0.90	0.90	4.86	$L = 3.90 - 0.90 = 3.00m$
	inter room wall	1	3.00	0.60	0.40	0.72	$L = 3.90 - 0.90 = 3.00m$
	square room -						
	Long wall (outer)	1	4.80	0.90	0.90	3.28	$L = 3.90 + 0.90 = 4.80m$
	short wall	2	3.00	0.90	0.90	4.86	$L = 3.90 - 0.90 = 3.00m$
	verandah pillar	2	0.90	0.90	0.90	1.46	
	verandah dwarf wall -						
	Long wall (front & back)	2	3.00	0.40	0.20	0.48	$L = 3.90 - 0.90 = 3.00m$
	short wall (front side)	1	1.10	0.40	0.20	0.09	$L = 2.00 - 0.90 = 1.10m$
	short wall (back side)	1	1.80	0.40	0.20	0.15	$L = 2.70 - 0.90 = 1.80m$
	step	1	1.20	0.70	0.10	0.08	
						Total =	32.99 cu.m
2.	Lime concrete in foundation -						
	Adjoining rooms combined -						
	Long walls -	2	10.10	0.90	0.30	5.45	L same as item (1)
	short walls	2	3.00	0.90	0.30	1.62	L same as item (1)
	inter room wall	1	3.40	0.60	0.20	0.41	$L = 3.90 - 0.50 = 3.40m$
	square room -						
	Long wall (outer)	1	4.80	0.90	0.30	1.30	$L = 3.90 + 0.90 = 4.80m$
	short wall	2	3.00	0.90	0.30	1.62	$L = 3.90 - 0.90 = 3.00m$
	verandah pillar	2	0.90	0.90	0.30	0.49	
	verandah dwarf wall -						
	Long wall (front and back)	2	3.50	0.40	0.10	0.28	$L = 3.90 - 0.40 = 3.50m$
	short wall front (side)	1	1.60	0.40	0.10	0.064	$L = 2.00 - 0.40 = 1.60m$
	short wall back (side)	1	2.30	0.40	0.10	0.092	$L = 2.70 - 0.40 = 2.30m$
	step	1	1.20	0.70	0.10	0.084	
						Total =	11.41 cu.m
3.	I-class brickwork in lime mortar in foundation and plinth -						
	Adjoining rooms combined -						
	Long walls -	2	9.80	0.60	0.20	2.35	$L = 9.20 + 0.60 = 9.80m$
	1st footing	2	9.70	0.50	0.20	1.94	$L = 9.20 - 0.10 = 9.70m$
	2nd footing	2	9.60	0.40	0.65	4.99	$L = 9.70 - 0.10 = 9.60m$
	plinth wall						
	short walls -						
	1st footing	2	3.30	0.60	0.20	0.79	$L = 3.90 - 0.60 = 3.30m$
	2nd footing	2	3.40	0.50	0.20	0.68	$L = 3.30 + 0.10 = 3.40m$
	plinth wall	2	3.50	0.40	0.65	1.22	$L = 3.40 + 0.10 = 3.50m$
	inter room wall						
	plinth wall	1	3.50	0.30	0.65	0.68	$L = 3.90 - 0.40 = 3.50m$
	square room in between						
	verandah						
	Long wall (outer) -	1	4.50	0.60	0.20	0.54	$L = 3.90 + 0.60 = 4.50m$
	1st footing	1	4.40	0.50	0.20	0.44	$L = 4.50 - 0.10 = 4.40m$
	2nd footing	1	4.30	0.40	0.65	1.12	$L = 4.40 - 0.10 = 4.30m$
	plinth wall						
	short wall -						
	1st footing	2	3.30	0.60	0.20	0.79	$L = 3.90 - 0.60 = 3.30m$
	2nd footing	2	3.40	0.50	0.20	0.68	$L = 3.30 + 0.10 = 3.40m$
	plinth wall	2	3.50	0.40	0.65	1.22	$L = 3.40 + 0.10 = 3.50m$
	verandah pillar						
	1st footing	2	0.60	0.60	0.20	0.15	
	2nd footing	2	0.50	0.50	0.20	0.10	
	plinth wall	2	0.40	0.40	0.65	0.21	
	verandah dwarf wall -						
	Long wall front and back	2	3.50	0.20	0.55	0.77	$L = 3.90 - 0.40 = 3.50m$
							$L = 2.00 - 0.40 = 1.60m$

Item No.	Particulars items work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
	short side wall (back) elev —	1	2.30	0.20	0.55	0.25	$L = 2.70 - 0.40 = 2.30m$
	1st step	1	1.20	0.60	0.15	0.11	
	and step	1	1.20	0.30	0.15	0.05	
						Total: 20.46 cu.m	
4.	25cm damp proof course —						
	Adjoining rooms combined —						
	Long walls	2	9.60	0.40	—	7.68	$L$ same as plinth wall
	short walls	2	3.50	0.40	—	2.80	
	Inter room wall	1	3.50	0.30	—	1.05	
	Square room —						
	Long wall (outer)	1	1.20	0.40	—	1.72	
	Short walls	2	3.50	0.40	—	2.80	
	verandah pillars	2	0.40	0.40	—	0.32	
	Deduct Door Sills —					Total: 16.37 sq.m	
	D <sub>1</sub>	4	1.00	0.40	—	1.60	
	D <sub>2</sub>	1	0.90	0.30	—	0.27	
						Total of deducts 1.87	
						Net Total = 14.50 sq.m	
5.	1st class brickwork in 1:6 cement mortar in superstructure						
	Adjoining rooms combined —						
	Long walls	2	9.50	0.30	3.62	20.63	Ht. up to top of slab
	short walls	2	3.60	0.30	3.62	7.83	Ht. up to top of slab
	Inter room wall	1	2.60	0.20	3.50	2.52	Ht. up to bottom of slab.
	Square room in between verandah —						
	Long wall (outer)	1	4.20	0.30	3.62	4.56	$L = 3.90 + 0.30 = 4.20m$
	verandah short wall	2	3.60	0.30	3.62	7.82	$L = 3.90 - 0.30 = 3.60m$
	verandah pillar	2	0.30	0.30	2.80	0.50	
	verandah 20cm wall above lintel —						
	Long wall	2	3.60	0.20	0.30	0.43	
	(front and back)						
	short wall front (side)	1	1.70	0.20	0.30	0.10	
	short wall back (side)	1	2.40	0.20	0.30	0.14	
	Parapet —						Ht. of parapet = $0.29 + 0.08 + 0.03 = 0.50m$
	Adjoining rooms —						
	outer longitudinal (out to out)	1	9.50	0.20	0.50	0.95	$L = 9.20 + 0.30 = 9.50m$
	short wall	2	4.00	0.20	0.50	0.80	$L = 3.60 + 0.30 + 0.10 = 4.00m$
	Front verandah side	1	2.40	0.20	0.50	0.24	$L = 1.20 + 0.60 = 2.40m$
	Back verandah side	1	2.50	0.20	0.50	0.25	$L = 2.50 + 0.20 - 0.20 = 2.50m$
	Square room — outer wall	1	4.20	0.20	0.50	0.42	$L = 3.60 + 0.60 = 4.20m$
	walls in between ver. and room	2	3.90	0.20	0.50	0.78	$L = 3.60 + 0.20 + 0.10 = 3.90m$
						Total: 47.96 cu.m	
	Deduct						
	Door openings —						
	D <sub>1</sub>	4	1.00	0.20	2.10	2.52	
	D <sub>2</sub>	2	0.90	0.20	2.10	0.38	
	window openings						
	W <sub>1</sub>	5	0.90	0.30	1.50	2.02	
	W <sub>2</sub>	1	1.80	0.30	1.50	0.81	
	shelves	4	0.90	0.20	1.80	1.30	
	Lintel over door, window and shelf.						
						0.567	Bracing ab. post slab not deducted may be deducted if specified
						Total deducting 7.60	



Particulars item of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanation Note
6. R.C.C. work 1:2:4 excluding steel and its bending, but including centering and shuttering and binding steel						
Roof slab -						
Adjoining rooms combined	1	9.20	3.90	0.12	4.206	Beaming 15cm
square room	1	3.90	3.90	0.12	1.825	Beaming 15cm
verandah front	1	4.05	2.15	0.10	0.871	Beaming 15cm
verandah back	1	4.05	2.85	0.10	1.154	
Verandah chajja -						
Front and back long	2	4.55	0.50	0.06	0.273	
side (front)	1	2.15	0.50	0.06	0.065	
side (back)	1	2.85	0.50	0.06	0.085	
Sunshades over windows						
W	4	1.20	0.40	0.06	0.115	
W <sub>1</sub>	1	2.10	0.40	0.06	0.050	
Lintels over doors, windows, shelves -						
Door D	4	1.20	0.20	0.10	0.1560	Beaming 15cm
Door D <sub>1</sub>	1	1.20	0.20	0.10	0.0240	Total ab(c) = 0.567 cum
window W	5	1.20	0.20	0.10	0.1200	
window W <sub>1</sub>	1	2.10	0.30	0.10	0.0630	
Shelves S	1	1.20	0.30	0.10	0.0420	
Verandah lintels						
front and back long	2	4.10	0.20	0.30	0.492	Beaming over wall 20cm
side (front)	1	2.00	0.20	0.30	0.120	
side (back)	1	2.70	0.20	0.30	0.162	
					Total = 10.085 cum	
7. Steel reinforcement bars including bending at 1%						
		10.085	100		cum = 0.1009 cum	
					@ 78.52/cum	
					= 0.1009 x 78.5	
					= 7.929	

### Centreline method

Three room building with front and back verandah


- Total centreline length of all 30cm walls - Total centreline lengths of two long walls and two outer short walls of the right side room (combined) and of the three walls of the remaining room (square room) =  $(2 \times 9.20 + 2 \times 3.90) + (3 \times 3.90) = 37.90$  mt.  
Number of junctions are 2 with 30cm walls.
- Total centreline length of 20cm interval = 3.90 mt.  
Numbers of junction are 2 with 30cm wall.
- Total centreline length of all 20cm walls of front and back verandah = Total centreline length of the front verandah long wall and side wall and of the back verandah long wall and side wall =  $(3.90 + 2.00) + (3.90 + 2.70) = 12.50$  m.  
Number of junction are 8 (4 with 30cm walls and 4 with 20cm pillars)
- Total length of parapet wall over outer walls of right side room and over outer walls of square room = Right side long wall + front and back outer walls + (walls by the right side of front and back verandah) + (outer walls of square room + front and back walls of square room) =  $(9.50 + 2 \times 4.00 + 2.40 + 2.50) + (4.20 + 2 \times 2.90) = 22.40 + 12.00 = 34.40$  m

Item No.	Particulars of item of work.	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation						
	All 30cm walls	1	37.00	0.90	0.9	29.97 cum	$L = 37.90 - 2 \times \frac{0.90}{2} = 37.00m$
	20cm internal wall	1	3.00	0.60	0.40	0.72	$L = 3.90 - 2 \times \frac{0.90}{2} = 2.00m$
	verandah pillars	2	0.90	0.90	0.90	1.46	
	All 20cm wall of verandah	1	8.90	0.40	0.20	0.71	$L = 12.50 - 8 \times \frac{0.90}{2} = 2.90m$
	step	1	1.20	0.60	0.10	0.07	
						Total: 32.93 cum.	
2.	Lime concrete in foundation						
	All 30cm walls	1	37.00	0.90	0.30	9.99	Length same as above
	20cm internal wall	1	3.00	0.60	0.20	0.41	$L = 3.90 - 2 \times \frac{0.90}{2} = 2.00m$
	verandah pillars	2	0.90	0.90	0.30	0.49	
	All 20cm wall of verandah	1	10.90	0.40	0.10	0.44	$L = 12.50 - 8 \times \frac{0.90}{2} = 10.90m$
	step	1	1.20	0.60	0.10	0.07	
						Total: 11.40 cum.	
3.	1-class brickwork in lime mortar in foundation and plinth.						
	All 30cm walls -						
	1st footing	1	37.40	0.60	0.20	4.48	$L = 37.90 - 2 \times \frac{0.60}{2} = 37.30m$
	2nd footing	1	37.40	0.50	0.20	3.74	$L = 37.90 - 2 \times \frac{0.50}{2} = 37.40m$
	20cm wall internal wall, plinth	1	3.50	0.30	0.65	0.68	$L = 8.90 - 2 \times \frac{0.40}{2} = 3.50m$
	Verandah pillars						
	1st footing	2	0.60	0.60	0.20	0.15	
	2nd footing	2	0.50	0.50	0.20	0.10	
	plinth wall	2	0.40	0.40	0.65	0.21	
	All 20cm wall verandah walls, plinth						
	steps -	1	1.20	0.60	0.15	0.11	
	1st	1	1.20	0.30	0.15	0.05	
	2nd					Total: 20.47 cum.	
4.	2.5cm Damp proof course -						
	All 30cm walls	1	37.50	0.40	-	15.00	
	20cm wall internal walls	1	3.50	0.30	-	1.05	
	verandah pillars	2	0.40	0.40	-	0.32	
						Total: 16.37	
	Deduct door sill	same as				1.87	
						Net Total: 14.50 cum.	
5.	1-class brickwork in 1:6 cement mortar in superstructure						
	All 30cm walls	1	37.60	0.30	3.62	40.83	$L = 37.90 - 2 \times \frac{0.30}{2} = 37.60m$
	20cm internal wall	1	3.60	0.20	3.50	2.52	$L = 3.90 - 2 \times \frac{0.30}{2} = 3.60m$
	verandah pillars	2	0.30	0.30	2.80	0.50	No. of junctions with 30cm walls
	All 20cm wall of verandah above						
	lintel including over pillars.	1	11.90	0.20	0.20	0.71	$L = 12.50 - 4 \times \frac{0.30}{2} = 11.90m$
	parapet wall walls	1	34.40	0.20	0.40	2.75	Total length of all walls
	20cm walls	1	34.40	0.25	0.10	0.86	
	25cm walls					Total: 48.17 cum.	
	Deduct doors and window openings & lintel	same as				7.60	
						Net Total: 40.57 cum.	



## ESTIMATE OF A HEXAGONAL ROOM


Hexagonal Room



Plan

### SCHEDULES :-

D-120 cm × 210 cm (1.20 m × 2.10 m)  
W-110 cm × 150 cm (1.10 m × 1.50 m)



CROSS SECTION OF WALL THROUGH DOOR

Fig. 3-11

Ans. The plan and part cross-section of a hexagonal room are given in (Fig 3.11). Estimate the quantities of - (1) Earthwork in excavation in foundation, (2) Lime concrete in foundation, (3) 1-class brickwork in foundations and plinth in lime mortar, (4) Damp proof course, (5) 1-class brickwork in superstructure in lime mortar, (6) R.C. work in roof including chhajja and lintels, (7) Lime concrete in roof terracing, by 2.5m c.c. over 7.5cm L.C. floor and (8) 12mm cement plastering 1:6 inside and outside walls.

Ans. The length of the centreline and the area of the hexagonal may be calculated as below. Fig 3.12 represents  $\frac{1}{2}$ th of the hexagon. The sides of a hexagonal form equilateral triangle at the centre.

$$\text{Length of centreline of one side } L_1 = 3.00 + 2 \times \frac{1.20}{\tan 60^\circ} = 3.00 + 2 \times \frac{0.20}{1.732} = 3.23 \text{ m}$$

$$\text{Therefore, total length of centreline} = 6 \times 3.23 = 19.38 \text{ m}$$


$$\text{outer length of superstructure wall } l_1 = 3.00 + 2 \times \frac{0.40}{\tan 60^\circ} = 3.00 + 2 \times \frac{0.40}{1.732} = 3.46 \text{ m}$$

$$\text{outer length of plinth wall} = 3.00 + 2 \times \frac{0.45}{\tan 60^\circ} = 3.00 + 2 \times \frac{0.45}{1.732} = 3.52 \text{ m}$$

$$\text{outer length of chhajja } l_2 = 3.00 + 2 \times \frac{0.85}{\tan 60^\circ} = 3.00 + 2 \times \frac{0.85}{1.732} = 3.98 \text{ m}$$

$$\begin{aligned} \text{Floor area} &= 6 \times \text{area of one inside triangle} \\ &= 6 \times \left( \frac{1}{2} \times \text{base} \times \text{altitude} \right) \\ &= 6 \times \left( \frac{1}{2} \times 3.00 \times 3.00 \times \frac{1}{2} \times \tan 60^\circ \right) \\ &= 6 \times \left( \frac{1}{2} \times 3 \times 3 \times \frac{1}{2} \times 1.732 \right) \\ &= 23.38 \text{ sq. m} \end{aligned}$$

$$\text{Roof area} = 6 \times \text{area of one outside triangle} = 6 \times \left( \frac{1}{2} \times 3.46 \times 3.46 \times \frac{1}{2} \times 1.732 \right) = 31.10 \text{ sq. m}$$



Item No.	Particulars of item of works	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation	1	19.38	0.90	1.00	17.44 cum	L = Total length of centreline 3/10 of excavation.
2.	Lime concrete in foundation	1	19.38	0.90	0.30	5.23 cum	
3.	1-class brickwork in foundation and plinth in lime mortar — Let footings and footing plinth wall	1 1 1	19.38 19.38 19.38	0.70 0.60 0.50	0.20 0.20 0.90	2.71 2.33 2.72	
						Total	13.76 cum
4.	2cm Damp proof course	1	19.38	0.50	—	9.69	
	Deduct door sill	1	1.20	0.50	—	0.60	
						Net Total	9.09 sq. m
5.	1-class brickwork in superstructure in lime mortar	1	19.38	0.40	3.50	27.12	10cm bearing
	Deduct —						
	Door opening	1	1.20	0.40	2.10	1.01	
	Window opening	5	1.10	0.40	1.50	3.30	
	Lintel over door	1	1.40	0.40	0.10	0.06	
	Lintel over windows	5	1.30	0.40	0.10	0.26	
						Total deduction	4.63
						Net Total	22.50 cum



Item No.	Particulars of item of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
6.	R.C.C. work complete with steel reinforcement - Roof slab chhajja Lintel						$6 \times \frac{1}{2} \times 3.46 \times \frac{3.46}{2} \times 1.73 = 4.013$ $6 \times \frac{3.46 \times 3.46}{2} \times 1.5708 = 0.603$ same as above i.e. 0.324 Total = 4.946 cum
7.	8cm lime concrete in roof terrace						same area as for R.C.C. roof
8.	2.4cm c.c. over and including 7.5cm L.C. floor						$6 \times \frac{1}{2} \times 3.46 \times 1.732 = 21.38$ sq.m
9.	12mm cement plastering 1:6 in walls. Inside outside above plinth outside plinth wall	6	3.00	-	3.50	63.00	
		6	3.46	-	3.50	72.66	
		6	3.50	-	6.70	14.72	including 10cm below a.l
						Total = 50.44	
	Deduct Door opening	1	1.20	-	2.10	2.52	
	Deduct window	5	1.10	-	1.50	8.25	ONE face.
						Total = 10.77	
						Net Total = 39.67 sq.m	

Ex. 9 From the attached plan and the detail of wall section (Fig B-13) estimate the quantities.

- Earthwork in foundation
- Concrete in foundation
- Brickwork in foundation and plinth in 1:6 cement mortar
- 2cm Damp proof courses at plinth level
- Brickwork in superstructure in lime mortar.
- 2.5cm c.c. over 4.5cm L.C. floor.

Ans centre to centre length of inclined wall

$$= \sqrt{(1.95 + 0.15)^2 + (1.125 + 0.15)^2}$$

$$= \sqrt{2.1^2 + 1.275^2} = \sqrt{6.04} = 2.46m \text{ (approximately)}$$

$$\text{Total centre line length of walls} = 4.80 + (2 \times 4.15) + (2 \times 2.46) + 2.25 = 20.27m$$

Item No.	Particulars item of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	Earthwork in excavation in foundation	1	20.27	0.90	0.90	16.42 cu.m.	L = Total centre length = 20.27m
2.	Concrete in foundation	1	20.27	0.90	0.30	5.47 cu.m.	
3.	Brickwork in foundation and plinth in 1:6 cement mortar -						
	1st footing	1	20.27	0.70	0.20	2.80	
	2nd footing	1	20.27	0.60	0.20	2.43	
	3rd footing	1	20.27	0.50	0.20	2.03	
	plinth wall	1	20.27	0.40	0.60	4.86	
						Total = 12.16 cu.m.	




Fig. 3-13



Particulars of items of work	Sl. No.	Length m	Breadth m	Height m	Quantity sq. m	Explanatory notes
1. 2.5 cm damp proof course Under door sill	1	2.50	0.10	—	2.50	
	1	1.25	0.10	—	0.12	
		1st Total			7.63	
					sq. m	
5. Brickwork in superstructure in lime mortar	1	20.27	0.20	2.70	28.50	
Deduct —						
Door opening	1	1.50	0.30	2.20	0.79	
Window opening	1	1.00	0.30	1.50	0.15	
Chalk	2	1.00	0.20	1.90	0.16	
Lintel over door	1	1.50	0.30	0.10	0.13	
Lintel over window	1	1.00	0.30	0.10	0.13	10 cm thick lintel
Lintel over chalk	2	1.00	0.30	0.10	0.13	10 cm thick lintel
		Total deduct			4.59	
		Net Total			17.91	
					sq. m	
6. 2.5 cm c.c. over 7.5 cm lime concrete floor.	1	4.50	1.00	—	10.00	
Rectangular portion	1	1.50	1.00	—	6.50	
Door sill	1	1.50	0.30	—	0.45	only 2.5 cm c.c.
		Total			21.00	
					sq. m	

### SLOPING ROOF

sloping roof may be of —

- Galvanized Corrugated Iron sheet (G.C.I. sheet)
- Asbestos cement sheet (A.C. sheet)
- Tiles
- Timber
- Planks, Thatch, and
- Slate

Ex 2 Prepare a detailed estimate of the verandah roof of a building from the given plan and sectional drawing (Fig 4.5). The verandah roof consists of 24 E.M. 6.82 sheets supported over salwood rafters and purlins. Woodwork shall be painted two coats over one coat of priming. Assume suitable rates.

Ex 3 Length of rafter, hip rafter and jack rafter may be calculated as below.

Rafter - Fig 4.5 (a)

$$\text{Length of rafter} = \sqrt{3.15^2 + 0.5^2} \times 1.02 = 3.32 \text{ m}$$

Adding 15 cm box insertion into wall length of rafter comes to 3.47 m. Sloping breadth of G.I. sheet rafter is  $3.32 \text{ m} + 15 \text{ cm} = 3.47 \text{ m}$  (5 cm outer projection beyond end of rafter).

Hip rafter - Fig 4.5 (b)

$$\text{Length of hip rafter} = \sqrt{3.15^2 + 3.32^2} = \sqrt{0.94} = 4.58 \text{ m}$$

Adding 15 cm box insertion into wall the length of hip rafter comes to 4.73 m.

Length of ridge (5 cm insertion into wall and 3 cm outer projection) =  $4.58 + 0.05 + 0.05 = 4.68 \text{ m}$

Jack rafter - Fig 4.5 (ii)

$$\frac{L}{3.32} = \frac{2.45}{2.15}$$

$$L = 3.32 \times \frac{2.45}{2.15} = 3.58 \text{ m}$$

Length of rafter is 3.58 m.






Fig. 4-5





PART PLAN SHOWING ARRANGEMENT OF REINFORCEMENT BARS

Fig. 5-4

**Note**—In plan bent up and top bars have been shown in dotted lines.

Sl. No.	Particulars of items of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	R.C.I. sheet roof in Verandah - Front side	1 1	$\frac{9.85+6.70}{2}$ $\frac{8.05+9.90}{2}$	3.37 3.37	— —	27.29 21.82	} Avg. length
						Total: 49.11 sq.m	
2.	Saluwood work - Main Rafter Hip Rafter Jack rafter purlin front purlin side Bressumer front Bressumer side	7 1 2 4 4 1 1	3.47 4.73 8.58 $\frac{8.58+7.70}{2}$ $\frac{8.58+7.70}{2}$ 7.30 7.50	0.10 0.10 0.10 0.05 0.05 0.10 0.10	0.15 0.15 0.15 0.08 0.08 0.15 0.15	0.364 0.071 0.077 0.132 0.134 0.140 0.113	} Front length  } Avg. length
						Total: 1.001 cu.m	
3.	16mm diameter H.D. Bolts 40cm long	10	—	—	—	10 nos	
4.	G.I. Ridge	1	4.68	—	—	4.68m	
5.	painting two coats wood work over a coat of priming - Main Rafter Hip Rafter Jack rafter Purlins front purlins side Bressumer front Bressumer side	7 1 2 4 4 1 1	3.47 4.73 2.53 8.215 8.475 9.20 7.50	0.50 0.50 0.50 0.26 0.26 0.50 0.50	— — — — — — —	17.64 8.61 6.73 8.40	} B = perimeter = 34.18 x 0.5 = 17.09  } Avg. length same as in item 2 16.8 x 0.5 = 8.40
						Total: 40.78 sq.m	

Ques 2 Prepare a detailed estimate of a R.C.C. Roofs slab of 3 meters clear span and 6 meters long from the given drawing (Fig 54). R.C.C. work including centering and shuttering and steel reinforcement in details shall be taken separately.

Sl. No.	Particulars of items of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Notes
1.	R.C.C. work 1:2:3 excluding steel and its bending but including centering and shuttering and binding steel	1	6.30	3.30	0.12	2.495 cum	No deduction for steel bar
2.	Steel bar including bending (mild steel in R.C.C. work - Main bar 12mm dia @ 0.89 kg/m straight bar 24cm c/c (Nb. = $\frac{6.30-0.08}{0.24} + 1 = 27$ ) Bent up bars 24cm c/c - (Nb. = $\frac{6.30-0.08}{0.24} = 26$ )	27 26	3.44 3.52				side cover 4cm L = 3.30 - 2 side covers + 2 hooks = 3.30 - 0.08 x 2 x 2 + 0.12 x 2 = 3.44m  folding one depth across bar two bent up.
						Total 126.40 @ 0.89 kg/m = 124.40 x 0.89 = 110.72 kg	






Fig. 5-8

Particulars item of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
Distribution bars 8mm (dia. @ 0.22m)						
Bottom bars central portion 18cm/c	12	6.33				$1 \times 6.33 \times 0.08 \times (12 \times 0.006) = 6.23m$
(No. = $\frac{7.00}{0.18} + 1 = 12$ )						
Bottom bars two sides	2x3	6.33				
Top bars two sides	2x3	6.33				
	Total	19.92 @ 0.22			kg	
		= 19.92 x 0.22			33.42	
					kg	
					Total = 197.54 kg	
					1975 sqm ft	

Prepare a detailed estimate of R.C.C. staircase from the given plan and section (Fig 9)

Item No.	Particulars of items of work	No.	Length in m	Breadth in m	Height in m	Quantity	Explanatory Note
1.	R.C.C. work 1:2:4 excluding steel and its bending but including centering and shuttering and binding steel						
	Base of flights in ground floor	1	1.20	0.50	0.25	0.150	$L = \sqrt{2.15^2 + 1.65^2} = 3.21m$
	slab of flights (inclined)	2	3.21	1.20	0.15	1.156	Bearing 15cm.
	Landing middle and first floor	2	2.70	1.35	0.15	1.087	
					Total	2.40	cu.m.
2.	Brickwork in steps in 1:4 cement mortar (cut brickwork)	2x11	1.20 x $\frac{1}{2}$	0.25 x 0.15		0.495	cu.m.
3.	20mm cement plaster 1:6 in steps finished neat						
	ceiling -	2x11	1.20 x (0.25 + 0.15)			10.56	
	Tread and rise	2x11 x $\frac{1}{2}$	(0.25 + 0.15)			0.111	
	Ends of steps				Total	10.77	sq.m.
4.	2.5cm nosing in steps in 1:3 cement mortar	2x12	1.20	—	—	28.80	m
5.	2.5cm c.c. floor 1:2:4 finished neat cement bleating in landings middle and first floor	2	2.70	1.20	—	6.48	sq.m
6.	steel work including bending in reinforcement and railing						
	(i) 12mm Dia. bars @ 0.89 kg/m						
	R.C.C. work - Main bars in lower flight and landing	11	5.22				$L = 4.10 + 0.90 + 0.18$ dia. = 5.00 + (18 x 0.12) = 5.22m
	No. of bars = $\frac{12.0}{1.2} + 1 = 11$ nos.						$L = 1.30 + 3.70 + 1.05 + 18 \times 0.12$ = 6.25m
	Main bars in upper flight and middle and first floor landings	11	6.25				$L = 1.08 + 0.61 + 4 \times 0.12 = 1.80m$
	Top bars first floor landings	11	1.20				$L = 1.20 + 0.15 - 2 \text{ corners} + 2 \text{ hooks}$ = 1.49m
	Extra bars first floor middle of each landing	2	1.49				
	Total	148.95	x 0.89	=		132.56	kg



Item No.	Particulars of item of work	No.	Length m	Breadth m	Height m	Quantity	Explanatory notes
	67.8mm Dia distributing bars @ 0.39 kg in R.C.C. work - 1 bar for flight 15 nos. and upper flight 14 nos. Middle landing 9 nos. and upper landing 9 nos.	27 17	1.27 2.77	}			L = 1.20 - 2 covers + 2 hooks = 2.27 L = 2.70 - 2 covers + 2 hooks = 2.77m.
(ii)	16mm sq bars in roofing @ 2.01 kg	47	0.90		2.1	8502 kg	No. (11x2x2) + 3 in middle landing = 47 nos.
					Total	250.3 kg 2.503 m	
7.	R.C.C. 1:2:4 hand rail inclusive reinforcement containing and chattering finished heat cement floating with moulding	1	6.82	-	-	6.82 m	L = 2x3.21 + 0.40 = 6.82 m
8.	R.C.C. 1:2:4 Newel posts including steel reinforcement and bonework finished Ground Floor first floor	1 1	1.80 0.90	0.10 0.10	0.10 0.10	0.81 0.01	
					Total	0.82 cum	
9.	Cap of Newel post of C.C.					2 nos.	

### Analysis of Rates:

The determination of rate per unit of a particular item of work, from the cost of quantities of materials, the cost of labourers and other miscellaneous petty expenses required for its completion is known as the analysis of rate. A reasonable profit usually 10% for the contractor is also included in the analysis of rate. Rates of materials are usually taken as the rates delivered at the site work and include the cost of transport, railway freight if any, taxes etc. If the materials are to be carried from a distant place, more than 8 kms (Stated), then cost of transport is also added. The rates of materials and labour vary from place to place and therefore, the rates of different items of work also vary from place to place.

For the purpose of analysis, the details about all the operations involved in carrying out the work should be available, the quantities of materials required and their costs should be known and the number of different categories of labourers required and the capacity of doing work per labourer and their wages per day should be known. These can be known only from experience of practical works.

Overhead costs. Overhead costs include general office expenses, rents, taxes, supervision and other costs which are indirect expenses and not productive expenses on the job.

The miscellaneous expenses on overheads may be under the following heads

#### A. General overheads:

- Establishment (Office staff)
- Stationary, printing, postages, etc.
- Travelling expenses
- Telephone
- Rent and taxes.

#### B. Job overhead

- Supervision (Salary of Engineer, Overseers, Supervision, etc.)
- Handling of materials
- Repairs, carriage and depreciation of T. and F.
- Amortisation of labour.



- (1) Interest on investment
- (2) Losses on advances

The Contractor may be allowed a net profit of 6 to 8%, and the miscellaneous overhead expenses may come to about 5 to 10%. Find overhead expenses and contractor's profit 15% of the actual cost may be reasonable amount but it is usual practice to add 10% percent for all these under the head profit. For small works overhead cost may be very little.

The analysis of rate is usually worked out for the unit of payment of the particular item of work under two heads -

- (a) Materials and
- (b) Labour

Task - The capacity of doing work by an artisan or skilled labour in the form of quantity of work per day is known as the task-work or out-turn of the labour.

The following may be taken as the approximate quantity of work or out-turn on task for an average artisan per day.

#### Particulars of item.

	Quantity	Per day
1. Brickwork in lime or cement mortar in foundation and plinth	1.25 cu.m	(45 cu.ft) per mason
2. - DO - in superstructure	1.00 cu.m	(35 cu.ft) per mason
3. Brickwork in mud mortar in foundation and plinth	1.50 cu.m	(55 cu.ft) per mason
4. - DO - in superstructure	1.25 cu.m	(45 cu.ft) per mason
5. Brick in cement or lime mortar in arches	0.55 cu.m	(45 cu.ft) per mason
6. - DO - in jack arches	0.55 cu.m	(20 cu.ft) per mason
7. Half brick wall in partition	5.00 sq.m	(50 sq.ft) per mason
8. Courshed rubble stone masonry in lime or cement mortar including dressing	0.20 cu.m	(30 cu.ft) per mason
9. Random rubble stone masonry in lime or cement mortar	1.00 cu.m	(35 cu.ft) per mason
10. Ashlar masonry in lime or cement mortar	0.40 cu.m	(15 cu.ft) per mason
11. Stone arch work	0.40 cu.m	(15 cu.ft) per mason
12. Lime concrete in foundation or floor	8.50 cu.m	(300 cu.ft) per mason
13. Lime concrete in roof terracing	6.00 cu.m	(200 cu.ft) per mason
14. Cement concrete 1:2:4	5.00 cu.m	(175 cu.ft) per mason
15. R.C. work	1.00 cu.m	(35 cu.ft) per mason
16. R.C.C. work	3.00 cu.m	(125 cu.ft) per mason
17. 12mm ( $\frac{1}{2}$ ") plastering with cement or lime mortar	8.00 sq.m	(80 sq.ft) per mason
18. pointing with cement or lime mortar	10.00 sq.m	(100 sq.ft) per mason
19. White washing or colour washing 3 coats	70.00 sq.m	(700 sq.ft) per white washer.
20. White washing or colour washing 1 coat	200.00 sq.m	(2000 sq.ft) per white washer.
21. Painting or varnishing doors or windows one coat	25 sq.m	(250 sq.ft) per painter.
22. coal terracing or solignum painting one coat	25.00 sq.m	(350 sq.ft) per painter.
23. Painting large surface one coat	35.00 sq.m	(350 sq.ft) per painter.
24. Distempereing one coat	35.00 sq.m	(350 sq.ft) per painter.
25. 2.5cm (1") C.C. floor	7.50 sq.m	(75 sq.ft) per painter.
26. Flag stone floor laying with lime or cement mortar excluding L.C.	10.00 sq.m	(100 sq.ft) per painter.
27. Terrazzo floor 6mm thick mosaic work over 2cm thick cement concrete (1:2:4)	5.00 sq.m	(50 sq.ft) per mason
28. Bridge-on-edge in floor lime or cement mortar excluding L.C.	7.00 sq.m	(70 sq.ft) per mason
29. Brick flat floor as in above	8.00 sq.m	(80 sq.ft) per mason
30. Timber flooring sal or teak wood	0.07 cu.m	(2.5 cu.ft) per Carpenter
31. - DO - sandalwood	0.15 cu.m	(6 cu.ft) per



Particulars of item	Quantity	Per day
32. Door and window shutters panelled or glazed	0.15 sqm	( <del>1.5 sqft</del> ) per carpenter
33. - DO - battened	0.20 sqm	8 sqft per carpenter
34. Sawing hard wood	1.00 sqm	(40 sqft) per pair of sawers
35. Sawing of soft wood	6.00 sqm	(60 sqft) per pair of sawers
36. Single Allahabad tiling or Mangalore tiling	6.00 sqm	(60 sqft) per tile layer
37. Double Allahabad tiling	1.00 sqm	(40 sqft) per tile layer
38. Breaking of brick ballast 40mm (1 1/2") gauge	0.75 cum	(80 cuft) per labourer or breaker
39. Breaking of brick ballast 25mm (1") gauge	0.55 cum	(20 cuft) per labourer or breaker
40. Breaking of stone ballast 40mm (1 1/2") gauge	0.40 cum	(15 cuft) per labourer or breaker

### LABOUR (MAZDOR) REQUIRED FOR DIFFERENT WORKS

Extracts from the report on productivity projects in building industries issued by National Building Organisation are given below

(a) Earthwork per 28.30 cum (1000 cuft).

(1) Excavation in foundations, trenches, etc. in ordinary soil including disposal upto 30m (100') and lift of 1.5m (5 ft) - 5 Beldars and 4 Mazdoors can do 28.30 cum (1000 cuft) per day.

(2) Refilling excavated earth in foundations plinth, etc. including consolidation in 15cm

(6") layers - 3 Beldars, 2 Mazdoors and 1/2 Bhisti can do 28.30 cum (1000 cuft) per day

(3) Disposal of surplus earth within a lead of 30m (100') - 1 Mazdoor can do 2.83 cum (100 cuft) per day.

(b) Cement concrete work per 2.83 cum (100 cuft).

Laying cement concrete - 2 Beldars, 3 Mazdoors, 3/4 Bhisti and 1/4 mason can do 2.83 cum (100 cuft) per day

(c) R.C.C. work -

(1) Laying reinforced concrete - 3 Beldars, 3 Mazdoors, 1 1/2 Bhisti and 1/2 mason can do 2.83 cuft (100 cuft) per day

(2) Centering and shuttering for flat surfaces - 4 Beldars, and 1 carpenter (11 class) can do 9.6 sqm (96 sqft) per day.

(3) Reinforcement work for R.C.C. - 1 Blacksmith or better and 1 Beldar can bend and place in position 1 quintal (2 cuft) of steel per day.

(d) Stonework per 2.83 cum (100 cuft)

Random rubble masonry with blue stone in foundation - 3 masons, 3 Beldars, 2 Mazdoors and 1/4 Bhisti can do 2.83 cum (100 cuft) per day.

(e) Brickwork per 2.83 cum (100 cuft)

First class brickwork in 1:4 cement mortar in superstructure partition walls, junctions of roofs, parapet walls, and string course - 2 1/4 masons, 4 1/2 Mazdoors, and 1/2 Bhisti can do 2.83 cum (100 cuft) per day.

(f) Woodwork -

(1) For the frames of doors and windows - 2 carpenters and 1 Beldar can work 0.18 cum (240 cuft) of wood equivalent to 4 door frames 7.5m x 10cm or 1.2m x 2.1m (3' x 4" or 3' - 11" x 7") size per day

(2) For panelled, glazed, etc. shutters - 15 carpenters and 4 Beldars can make and fix 4 shutter 40cm thick of size 2.00m x 1.15m (1 1/2" thick of size of 6' - 9" x 3' - 9") per day. Quantity of wood per shutter - 0.075 cum i.e. 2.66 cuft

(g) Iron work -

(1) Fixing 40mm x 3mm x 38cm (1 1/2" x 1/8" x 15") flat iron holdbasts - 1 Blacksmith (11 class) 1 mason, and 1 Beldar can fix 36 holdbasts per day.

(2) Fixing 16mm dia (5/8") dia iron rods - 1 Blacksmith (11 class) 2 masons, and 1 Beldar can fix 36 rods per day.



(4) Flooring - 4cm thick (1½") thick cement concrete flooring of 40 sq.m (400 sq.ft) require - 5 masons, 4 Beldar, 3 Mazdoors and 1 Bhisti per day for mixing, laying and finishing.

(5) Finishing -  
 (a) plastering with any mortar 12mm (½") thick - 3 masons, 3 Mazdoors and 1 Bhisti can plaster 40 sq.m (400 sq.ft) per day.  
 (b) White washing or colour washing (3 coats) - 1 white washer and 1 Mazdoor can do 60 sq.m (600 sq.ft) per day.  
 (c) Painting two coats such as chocolate, red, grey etc. on wood or steel - 3 painters and 2 Mazdoors can paint 10 sq.m (100 sq.ft) per day.

1 cu.m. portland cement (ordinary cement) = 1.44 grams i.e. 1 cu.m. of portland cement = 1440 kgs.

As per IS: 456 one litre (1 cu. decimeter) of portland cement = 1.44 kg

1 cu.m. of portland cement = 30 bags for practical purposes.

1 bag cement of 50 kg =  $\frac{1}{30}$  cu.m. = 0.034 cu.m.

At Rs. 215.00 per bag the cost of 1 cu.m. of cement comes to Rs. 6325.00

1 quintal (100 kg) white or stone lime

✓ 1. Time concrete in Foundation with 40mm gauge Brick Ballast unit 1 cu.m.  
 Take - 10 cu.m.

(a) With white lime and surkhi 1:2 (proportion - 16:32:100, i.e. 1:2:6 approx)

Particulars	Qty or Nos.	Rate	Cost
Materials -		Rs. P.	Rs. P.
Brick ballast 1 class 40mm gauge	10 cu.m.	400.00 cum	4000.00
White lime slaked	1.6 cu.m.	700.00 cum	1120.00
surkhi	3.2 cu.m.	350.00 cum	1120.00
		Total.	6240.00
Labour -			
Mistree (Head mason)	$\frac{1}{2}$ no.	160.00 per day	80.00
Mason	1 no.	150.00 per day	150.00
Mazdoor (Beldar)	12 nos.	80.00 per day	960.00
Boy or women coolie	12 nos.	70.00 per day	840.00
Bhiste (water-man)	2 nos.	70.00 per day	140.00
Sundries T. and P. etc. (misc. petty things)	Lump sum	45.00 L.S.	45.00
		Total	2215.00

Total of materials & labour = 8455.00

Add 1½% water charges

Add 10% contractor profit

127.00

845.00

Rate per cu.m. =  $\frac{9427.50}{10}$  = Rs. 942.75

Grand Total = 9427.50

Approximate calculation of materials for 100 cu.m. L.C. 1:2:6 lime = 150 for 10 cu.m.

surkhi =  $16.6 \times 2 = 32.2$  cu.m., Brick ballast =  $16.6 \times 6 = 99.6$  cu.m.

In practice these are taken as 16 cu.m.

$\frac{150}{1+2+6} = 16.6$  cu.m.

(b) With Kankar Lime (55% mortar) - unit 1 cu.m. Take - 10 cu.m.

Particulars	Qty or Nos.	Rate	Cost
Materials -		Rs. P.	Rs. P.
Brick ballast 1 class 40mm gauge	10 cu.m.	400.00 cum	4000.00
Kankar lime	3.5 cu.m.	400.00 cum	1400.00
		Total	5400.00
Labour -			
same as above (item 1-a)			2215.00

Total of materials & labour = 7615.00



Add  $1\frac{1}{2}\%$  water charges  
Add 10% contractor's profit

114.00  
761.50  
Grand total = 8490.50

Rate per cum = Rs. 8490.50/10 = 849.00 for 10 cum

1.6) With kankar lime and surkhi of 1:1 proportion = 10 cum.  
Brick ballast 40 mm gauge 10 cum, kankar lime 2.2 cum and surkhi 2.2 cum. and labour same as above.  
In place of brick ballast, stone ballast may also be used where stone ballast is cheap, which is usually in hill areas.

2. Lime concrete in Foundation or Floor with 40 mm gauge stone ballast, white lime and sand (Proportion 1:2:4) unit 1 cum. Take = 10 cum.

Materials -			
stone ballast 40mm gauge (local)	8.8 cum	900.00 cum	7920.00
Sand or bajri (local)	9.4 cum	400.00 cum	1760.00
white lime slaked	2.2 cum	700.00 cum	1540.00
Labour -			
same as for above (item 1-r)		Total	11220.00
			2215.00

Total of materials and labour = 13435.00  
Add  $1\frac{1}{2}\%$  water charges 201.00  
Add 10% contractor's profit 1343.00  
Grand total = 14979.00 for 10 cum

Rate per cum = Rs. 14979.00/10 = Rs. 1498.00

Approximate method of calculation of materials for 100 cum. L.C. 1:2:4 = Lime =  $\frac{152}{1+2+4}$  = 22 cum. sand =  $22 \times 2 = 44$  cum. stone aggregate =  $22 \times 4 = 88$  cum.  
That is for 100, 88:44:22 as stone aggregate: sand: Lime

3. Lime concrete in Terraced Roof with 25 mm gauge Brick ballast unit 1-1 cum. Take = 10 cum.  
(a) With white lime and surkhi - 1:2 (proportion) 18:36:100 i.e. 1:2:5.5 approximately

Materials -			
Brick ballast 2 class 25mm gauge	10 cum	450.00 cum	4500.00
white lime slaked	1.8 cum	700.00 cum	1260.00
surkhi	3.6 cum	350.00 cum	1260.00
Molasses (Gru)	12 kg	15.00 kg	180.00
Beil fruit (7 kg) in solution	Lump sum	35.00 L.S.	35.00
Labour -			
Mistral Head mason	$\frac{1}{2}$ no.	Total	7235.00
Mason	2 no.	160.00 per day	80.00
Mazdoor (beldar)	20 nos.	150.00 per day	3000.00
Boy or women coolie	25 nos.	80.00 per day	800.00
Bhisti (water-man)	3 nos.	70.00 per day	1750.00
Sundries T. and P. etc	Lump sum	70.00 per day	210.00
		45.00 L.S.	45.00
		Total	3185.00

Total of materials and labour = 10420.00  
Add  $1\frac{1}{2}\%$  water charges 156.30  
Add 10% contractor's profit 1042.00  
Grand Total = 11618.30 for 10 cum

Rate per cum = Rs. 11618.30/10 = Rs. 1162.00

(b) Rate per sqm. for 10 cm thick L.C. Terracing  
1 cu.m. for 10 cm thickness covers  $\frac{1}{0.1} = 10$  sqm. Rate per sqm.  $\frac{1162.00}{10} = Rs. 116.20$   
(c) Rate per sqm. for 7.5 cm thick L.C. Terracing  
1 cu.m. for 7.5 cm thickness covers  $\frac{1}{0.075} = 13\frac{1}{3}$  sqm. Rate per sqm.  $\frac{1162.00}{13\frac{1}{3}} = Rs. 87.11$



calculation of materials (approximate)

$$\text{Lime} = \frac{154}{172154} = \frac{154}{85} = 18.2 \text{ cum}, \text{ surkhi} = 18.2 \times 2 = 36.4 \text{ cu.m.}$$

$$\text{Brick ballast} = 18.2 \times 5\frac{1}{2} = 100 \text{ cu.m. Approximately } 18:36:100.$$

8(b) With kankar lime (45% mortar) - unit 1 cum. Take - 10 cu.m.

Materials -

Brick ballast 1-class 25 gauge

kankar lime

molasses (6%)

Bail fruit (7% in solution)

Labour -

same as for above (item 3 a)

10 cum	450.00 cum	4500.00
4.5 cum	450.00 cum	1800.00
15 kg	15.00 kg	180.00
Lump sum	45.00 L.S.	45.00

Total 6525.00

3185.00

Total materials & labour

9710.00

Add 1 1/2% water charges

145.00

Add 10% contractor's profit

971.00

Grand Total

10826.50

$$\text{Rate per cum} = \text{Rs. } 10826.50 / 10 = \text{Rs. } 1082.65 \text{ for 10 cu.m.}$$

$$\text{a) Rate per sqm for 10cm thick L.C. terracing} = 1082.65 / 10 = \text{Rs. } 108.26$$

$$\text{ii) Rate per sqm for 7.5cm thick L.C. terracing} = 1082.65 / 13\frac{1}{2} = \text{Rs. } 80.40$$

### Cement Concrete

Sum total quantity of determining the quantity of materials for 10 cum concrete is to divide 15.2 by the sum of the numerals of the proportions of the materials which gives the quantity of cement in cum.

Illustration - To find the materials for 10 cum. of cement at 1:4:8 proportion

$$\text{cement} = \frac{15.2}{1+4+8} = \frac{15.2}{13} = 1.17 \text{ cum} = \text{say } 1.15 \text{ cum.}$$

$$\text{Therefore, sand} = 1.15 \times 4 = 4.60 \text{ cu.m. and ballast} = 1.15 \times 8 = 9.20 \text{ cu.m.}$$

Materials required for different proportions of cement concrete - 10 cum.

Quantity of materials may be calculated by 15.2 as sum total and dividing by sum of the proportions

Proportion	Ballast	Sand	Cement
1:1 1/2:3	8.40 cum	4.20 cum	2.80 cum (28 bags)
1:2:4	8.80 cum	4.40 cum	2.20 cum (22 bags)
1:3:6	9.00 cum	4.50 cum	1.50 cum (15 bags)
1:4:8	9.20 cum	4.60 cum	1.15 cum (34 1/2 bags)
1:5:10	9.50 cum	4.75 cum	0.95 cum (28 1/2 bags)
1:6:12	9.60 cum	4.80 cum	0.80 cum (24 bags)

5 Cement concrete 1:5:10 in foundation on Floor with Brick ballast 40mm (1 1/2") Thick gauge. - unit 1 cum. Take - 10 cum.

Particulars	Qty or No.	Rate P.	Cost P.
Materials -			
Brick ballast 1st class 40mm gauge	9.50 cum	400.00 per cum.	3800.00
Sand	4.75 cum	400.00 per cum.	1900.00
Cement (28 1/2 bags)	0.95 cum	6225.00 per cum.	6008.75
Labour -			
Mistri (Head mason)	1/2 no.	160.00 per day	80.00
Mason	1 1/2 no.	150.00 per day	225.00
Mazdoor (Beldar)	12 nos.	80.00 per day	960.00
Boy or woman cooler	18 nos.	70.00 per day	1260.00
Bhathi (including curing)	4 nos.	20.00 per day	80.00
Lump sum		55.00 L.S.	55.00
Total			11708.75



Total = 2860.00

Total of materials and labour = 14568.75

218.50

1456.90

Add 1 1/2% water charges  
Add 10% contractor's profit

Rate per cum = Rs. 16244.15/10 = Rs. 1624.00

Grand Total = 16244.15  
for 10 cum

1/2 Cement concrete 1:2:4 - and 1 cum Taxe - 10 cum

Materials -

stone ballast 40mm gauge  
sand (coarse)  
cement (66 bags)

8.80 cum  
4.40 cum  
2.20 cum

900.00 per cum  
700.00 per cum  
6325.00 per cum

7996.00

3080.00

13915.00

Total = 24915.00

Labour

Mistri (Head mason)

Mason

Mazdoor (Beldar)

Boyan woman coolie

Bhicti (including curing)

Forms etc. (according to requirement)

Sundries T and P. etc.

1/2 nos.  
2 nos.  
12 nos.  
20 nos.  
6 nos.

160.00 per day  
150.00 per day  
80.00 per day  
70.00 per day  
70.00 per day  
600.00 L.S.  
70.00 L.S.

5330  
300.00  
960.00  
1400.00  
420.00  
600.00  
70.00

Total = 3803.20

Total of materials & labour

28718.20

Add 1 1/2% water charges

420.70

Add 10% contractor's profit

2871.80

Rate per cum = Rs. 32020.00/10 = Rs. 3202.00

for 10 cum.

Grand Total = 32020.80

F.R.C.C. work in Beams, slabs, etc. 1:2:4 - unit 1 cum Taxe - 1 cum

Particulars	Qty in Nos	Rate Rs. P.	Cost Rs. P.
<b>Materials -</b>			
stone ballast 20mm gauge	2.80 cum	1000.00 per cum	2800.00
sand (coarse)	4.40 cum	700.00 per cum	3080.00
cement (66 bags)	2.20 cum	6325.00 per cum	13915.00
steel, mild steel bars @ 1% = 1 cum. @ 78.5 g/cum = 7.85 kg	7.85 kg	3000.00 per kg	23550.00
Binding wire	1.50 kg	40.00 per kg	60.00
		<b>Total</b>	<b>19405.00</b>
<b>Labour -</b>			
Mistri (Head mason)	1/2 no.	160.00 per day	80.00
Mason	3 nos.	150.00 per day	450.00
Mazdoor (Beldar)	12 nos.	80.00 per day	960.00
Boyan woman coolie	20 nos.	70.00 per day	1400.00
Bhicti (including curing)	6 nos.	70.00 per day	420.00
Sundries T. and P. etc.	Lumpsum	60.00 L.S.	60.00
		<b>Total</b>	<b>3370.00</b>
Bending, cranking and binding steel bars in position -	8 nos.	150.00 per day	1200.00
Blacksmith (1st class)	8 nos.	80.00 per day	640.00
Mazdoor (Beldar)	Lumpsum	30.00 L.S.	20.00
T. and P.		<b>Total</b>	<b>1870.00</b>
Centering and shuttering (both erection and dismantling) -	Lumpsum	650.00 L.S.	650.00
Timber planks and ballies carpenter (1st class)	10 nos.	150.00 per day	1500.00
Mazdoor (Beldar)	10 nos.	80.00 per day	800.00
Nails	Lumpsum	90.00 L.S.	90.00
		30.00 L.S.	30.00



Total of materials and labour  
Add 1 1/2% water charges  
Add 10% contractor profit

57715.00  
865.00  
57715.00

Grand Total = 64352.00 for 10 cum.  
Rate per cum = Rs. 6435.20/10 = Rs. 6435.20

Brickwork with standard brick - Calculation of materials required for brickwork -

Take a wall 1/2 brick 20cm nominal thickness at 20m length and 5m height. Normally  
volume =  $20 \times 0.3 \times 5 = 30 \text{ cum}$

Normally mortar joint will be less than 1cm, taking 1cm mortar joint, the actual thickness of wall be 29cm.

Therefore, actual volume =  $20 \times 0.29 \times 5 = 29 \text{ cum}$ . Number of standard bricks of  $20\text{cm} \times 10\text{cm} \times 10\text{cm}$  nominal size =  $\frac{29}{0.20 \times 0.10 \times 0.10} = 14500 \text{ nos.}$

Therefore, number of bricks per cum (nominal) =  $\frac{14500}{30} = 484 \text{ nos}$ . Considering 5% breakage, wastage, etc. this may be taken 500 nos per cum.  
For 10 cum of brickwork 5000 bricks are required.

Mortar - Mortar requirement = total volume of brickwork minus net volume of bricks  
=  $29 - (0.19 \times 0.09 \times 0.09 \times 14500) = 29 - 2.215 = 6.685 \text{ cum}$ . For frog telling, for use of cut bricks, bonding, for uniform joints, wastage, etc. 15% extra mortar may be required. Therefore the volume of mortar =  $6.685 + 6.685 \times 0.15 = 7.688 \text{ cum}$ . For dry volume increase by 1/4 dry volume of mortar =  $7.688 + 1.922 = 9.61 \text{ cum}$ .

For 30 cum of brickwork, dry volume of mortar = 9.61 cum.

For 10 cum of brickwork, dry volume of mortar =  $9.61 \times \frac{10}{30} = 3.2 \text{ cum}$ .

In practice, for cement mortar 3 cum dry mortar and lime mortar 3.5 cum. of dry mortar are taken for 10 cum brickwork. As an example 30% dry mortar may be taken.

Calculation of materials of mortar -

Approximate method to determine the quantity of materials of mortar for 10 cum. brickwork. Divide 3 by the sum of the numerals of the proportion of materials which gives the quantity of cement in cum. As an example for brickwork in 1:6 cement mortar cement =  $\frac{3}{1+6} = 0.43 \text{ cum}$ . Therefore sand =  $0.43 \times 6 = 2.58 \text{ cum}$ . But as the cement will go to fill up the void in sand 0.45 cum of cement and 2.7 cum. of sand may be taken.

I-class Brickwork in Foundation and plinth with 20x10x10cm (nominal size) Bricks with cement sand mortar 1:6 - unit 1 cum. Take - 10 cum.

Particulate	Qty in Nos.	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials -</u>					
Brick 1-class (500 bricks per cum)	5000 nos.	2000.00 per 1000 nos		10000.00	
cement (13.5 bags)	0.45 cum	6325.00 per cum		2846.25	
sand (local)	2.7 cum	400.00 per cum		1080.00	
			Total	13926.25	
<u>Labour -</u>					
Mistri (head mason)	1/2 no.	160.00 per day		80.00	
Mason	7 nos.	150.00 per day		1050.00	
Mazdoor (Beldar)	7 nos.	80.00 per day		560.00	
Boy or woman coolie	7 nos.	70.00 per day		490.00	
Phusti (water man)	2 nos.	70.00 per day		140.00	
Sundries T. and P. etc. (Misc. Petty things)	Lumpsum	35.00 L.S.		35.00	
			Total	2355.00	

Total of materials and labour = 16281.25

Add 1 1/2% water charges = 244.25

Add 10% contractor profit = 1628.00



15. 1-class Brickwork in superstructure with 20x10x10 cm Brick with 1:6 cement sand Mortar - unit 1 cu.m. Tax - 10 cu.m.

Particulars	Qty or Nos	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials-</u>					
Brick 1-class (500 bricks per cu.m)	5000 nos.	2000.00 per / nos		10000.00	
cement (13.5 bag)	0.45 cu.m	6325.00 per cu.m		2946.25	
sand (Local)	2.7 cu.m	400.00 per cu.m		1080.00	
<u>Labour-</u>					
Mistri (Head mason)	1/2 nos.	160.00 per day		80.00	
Mason	10 nos.	150.00 per day		1500.00	
Mazdoor (Beldar)	7 nos.	80.00 per day		560.00	
Boy or woman coolie	10 nos.	70.00 per day		700.00	
Bhisti	2 nos.	70.00 per day		140.00	
Scaffolding	Lumpsum	130.00 L.S.		130.00	
Sundries, T and P. etc.	Lumpsum	35.00 L.S.		35.00	
			Total	3145.00	

Add 1/2% water charges  
Add 10% Contractor profit

Total of materials and labour 17071.25  
256.00  
1707.00

Grand Total = 19034.25  
Rate per cu.m - Rs. 19034.25/10 = Rs. 1903.00 for 10 cu.m

16. Half Brick wall (10 cm thick partition wall) with 1:3 cement mortar - unit 1 sq.m.  
Tax - 100 sq.m.  
100 sq.m. wall of 10 cm thickness = 10 cu.m hence quantity of materials may be calculated as usual

Particulars	Qty or Nos	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials-</u>					
Brick 1-class (500 nos. per cu.m)	5000 nos.	2000.00 per / nos		10000.00	
cement (22 1/2 bags)	0.75 cu.m	6325.00 per cu.m		4743.75	
sand coarse	2.25 cu.m	700.00 per cu.m		1575.00	
Mild steel bars 6mm dia. every 4th layer or hoop iron	40 kg	30.00 per kg		1200.00	
<u>Labour-</u>					
Mistri (Head mason)	1/2 no.	160.00 per day		80.00	
Mason	12 nos.	150.00 per day		1800.00	
Mazdoor (Beldar)	8 nos.	80.00 per day		640.00	
Boy or woman coolie	10 nos.	70.00 per day		700.00	
Bhisti	2 nos.	70.00 per day		140.00	
Scaffolding	Lumpsum	160.00 L.S.		160.00	
Sundries T and P. etc.	Lumpsum	35.00 L.S.		35.00	
			Total	3555.00	

Add 1/2% water charges  
Add 10% Contractor profit

Total materials & labour 21073.75  
316.00  
2107.25

Grand Total: 23497.00

19. 2nd class Brickwork in Mud Mortar in Superstructure - unit 1 cum. Take - 10 cum

### Materials -

Brick 2nd class  
Earth (loamy soil) including  
wastage

### Labour, etc. -

Mistri (Head mason)  
Mason  
Mazdoor (Beldar)  
Boy or woman coolie  
Bhisti  
Scaffolding  
Sundries T. and P. etc.

5000 nos.  
~~5.00 cum~~  
5.00 cum

$\frac{1}{2}$  no.  
8 nos.  
6 nos.  
6 nos.  
1 no.  
Lumpsum  
Lumpsum

2000.00 per 1000 nos. 10000.00  
15.00 per cum 75.00

Total = 10075.00

160.00 per day 40.00  
150.00 per day 1200.00  
80.00 per day 920.00  
70.00 per day 420.00  
70.00 per day 70.00  
140.00 L.S. 140.00  
35.00 L.S. 35.00

Total = 2285.00

Total of materials and labour = 12460.00

Add  $1\frac{1}{2}\%$  wastage-water charges.  
Add 10% Contractor's profit

187.00  
1246.00

Grand Total = 13893.00  
for 10 cum.

Rate per cum - Rs. 13893.00/10 = Rs. 1389.00

23. Crushed Rubble stone masonry in superstructure in 1:6 Cement Sand Mortar - unit 1 cum. Take - 10 cum.

Particulars	Qty or Nos.	Rate		Cost	
		Rs.	P.	Rs.	P.
<b>Materials -</b>					
Stone including through bond	12.50 cum	500.00	per cum	6250.00	
Stone and wastage	0.60 cum	6325.00	per cum	3795.00	
Cement (18 bags)	3.60 cum	400.00	per cum	1440.00	
Sand or bajri (local)					
			Total	11485.00	
<b>Labour, etc. -</b>					
Mistree (Head mason)	$\frac{1}{2}$ no.	160.00	per day	80.00	
Mason	16 nos.	150.00	per day	2400.00	
Mazdoor (Beldar)	16 nos.	80.00	per day	1280.00	
Coolie (boy or woman)	8 nos.	70.00	per day	560.00	
Bhisti	$1\frac{1}{2}$ nos.	70.00	per day	105.00	
Scaffolding	Lumpsum	160.00	L.S.	160.00	
Sundries T. and P. etc.	Lumpsum	35.00	L.S.	35.00	
			Total	4620.00	

Total of materials and labour

Add 10% Contractor's profit

Grand Total

16105.00  
1610.50

17715.50  
for 10 cum

Rate per cum - Rs. 17715.50/10 = Rs. 1771.50



## PLASTERING

### Calculation of quantity of mortar and materials -

Area  $\times$  thickness gives the quantity of mortar for uniform thickness. To fill up the joints and to make up uniform surface of wall, this may be increased by 30% which will give wet mixed mortar. To get the total dry volume of ingredient materials or mortar the wet volume may be further increased by 25%. The quantity of each material of the mortar may be found by usual methods, dividing the dry volume of mortar by the sum of the numerals of the proportion and multiplying by the individual numerals.

Materials for 12mm thick plastering in wall for 100 sq.m -

Wet mixed mortar for uniform layer = 1.2 cu.m. Adding 30% to fill up joints, uneven surfaces, etc. the quantity of mortar comes to 1.2 to 0.36 = 1.56 cu.m. Increasing by 25% the total dry volume = 1.95 cu.m = 2.00 cu.m (say). For 1:6 cement sand mortar, Cement =  $\frac{2}{1+6} = 0.30$  cu.m, sand =  $0.30 \times 6 = 1.80$  cu.m. Similarly, the quantities of materials for other proportions may be calculated. The quantities of materials for different proportions are given in the following page.

Materials for 20mm thick plastering in wall for 100 sq.m -

As the thickness of plaster is more, 20% of mortar may be taken to fill up the joints, unevenness, etc. The quantity of wet mortar is equal to  $2.00 \times 0.02 + 20\% = 2.00 + 0.40 = 2.40$  cu.m. Increasing 25% the dry volume:  $2.40 + 0.60 = 3.00$  cu.m. The quantities of each material of mortar may be found by usual method.

Rich Mortar - For rich mortar plastering, the quantities of materials will be less as the cement will be in excess than the voids in sand and the reduction in volume of dry mortar will be less.

Ceiling plastering 12mm thick for 100 sq.m - For plastering in R.C.C. ceiling the unevenness of surface will be less and 20% extra mortar may be taken to get unevenness even surface. The quantity of wet mortar is equal to  $100 \times 0.012 + 20\% = 1.2 + 0.24 = 1.44$  cu.m. Increasing by 25% the dry volume =  $1.44 + 0.36 = 1.80$  cu.m.

For 6mm thick plastering R.C.C. ceiling the quantity of dry mortar may be taken as 1.00 cu.m.

For plastering in floor over lime concrete the same quantity of mortar as for wall may be taken as there will be sufficient unevenness in the surface of lime concrete.

Heat cement flooring - For neat cement finishing in floor or dado or skirting, the thickness of neat cement layer may be taken as 15mm ( $\frac{1}{8}$ ) thick, therefore, the cement paste requirement for 100 sq.m =  $100 \times 0.0015 = 0.15$  cu.m. Dry volume of cement increased by 25% =  $0.15 + 0.15 \times \frac{1}{4} = 0.19$  cu.m = 2 cu.m (say) = 6 bag per 100 sq.m.



Materials required for plastering with different mortars of various proportions for 100 sq.m -

For 12mm thick plastering total dry volume 2 cum -

Mortar	Proportion	Cement	Sand
(i) Cement mortar	1:2	0.60 cum (18 bags)	1.20 cum
(ii) Cement mortar	1:3	0.45 cum (13½ bags)	1.35 cum
(iii) Cement mortar	1:4	0.40 cum (12 bags)	1.60 cum
(iv) Cement mortar	1:5	0.35 cum (10½ bags)	1.75 cum
(v) Cement mortar	1:6	0.30 cum (9 bags)	1.80 cum
(vi) Kankar lime	-	1.80 cum Kankar lime	-
(vii) White lime and surkhi or sand	1:1	1.00 cum white lime	1.00 cum surkhi or sand
(viii) White lime and surkhi or sand	1:2	0.70 cum white lime and surkhi or sand	1.40 cum
(ix) Cement, white lime and sand	1:1:6	0.30 cum cement, 0.30 cum lime and	1.80 cum sand

For 20mm thick plastering total dry volume 3 cum

(i) Cement mortar	1:2	1.00 cum (30 bags)	2.00 cum
(ii) Cement mortar	1:3	0.78 cum (21.4 bags)	2.34 cum
(iii) Cement mortar	1:4	0.65 cum (19½ bags)	2.60 cum
(iv) Cement mortar	1:5	0.54 cum (16.2 bags)	2.76 cum
(v) Cement mortar	1:6	0.46 cum (13.8 bags)	2.76 cum

\* 12mm plastering 1:6 - unit 1 sq.m. Take = 100 sq.m.

Particulars	Qty or Nos	Rate	Cost
		Rs.	P.
<u>Materials</u> -			
Cement (9 bags)	0.30 cum	6325.00 per cum	1897.50
Sand (10 cu)	1.80 cum	400.00 per cum	720.00
<u>Labour etc</u>			
Mistri (Head mason)	1/3 no.		
Mason	10 nos.	160.00 per day	53.30
Mazdoor (Beldar) including raking of joints	15 nos.	150.00 per day	1500.00
Bhisti including carrying	3/4 nos.	80.00 per day	1200.00
Scaffolding sundries T. and P.	Lumpsum	70.00 per day	52.50
		90.00 l.s.	90.00
		<b>Total</b>	<b>2617.50</b>

Total of materials and labour  
Add 1½% water charges  
Add 10% contractor's profit

5513.30
82.70
551.30
<b>Grand Total</b>
<b>6147.30</b>
for 100 sq.m

Rate per sq.m - Rs. 6147.30/10 = Rs. 615.00

20. 12mm thick plastering 1:3 cement coarse and mortar - surface neat cement finished in dado - unit 1 sq.m. Take - 100 sq.m.

Materials

Cement (13½ bags)	0.45 cum
Sand coarse	1.35 cum
Cement for surface finishing (6 bags)	0.20 cum

Labour -

Mistri (Head mason)	1/3 nos.
Mason	12 nos.
Mazdoor (Beldar)	15 nos.
Bhisti	1 no.
Sundries T. and P.	30.00

Add 1½% water charges and 10% contractor's profit over total cost



## Cement Concrete floor

The quantity of cement concrete may be calculated by multiplying area of floor thickness and the quantity of each material may be found on the same principle as for cement concrete.

For 2.5 cm c.c. floor for 100 sq.m. of area the quantity of cement concrete =  $100 \times 0.025 = 2.5 \text{ cu.m}$ . Adding 10% extra for unevenness of base concrete, the quantity comes to  $2.5 + 0.25 = 2.75 \text{ cu.m}$ .

For 100 cu.m cement concrete the total dry volume of materials is 125, i.e. approximately 50% more.

For 2.5 cm thick c.c. floor of 1:2:4 proportion, for 100 sq.m. total dry volume of materials =  $2.75 + 50\% = 2.75 + 1.375 = 4.125 \text{ cu.m}$ . Therefore, cement =  $\frac{4.125}{1+2+4} \times \frac{4.125}{7} = 0.59 \text{ cu.m} = 0.60 \text{ cu.m}$  (12 bags), sand =  $0.6 \times 2 = 1.20 \text{ cu.m}$  and stone aggregate =  $0.6 \times 4 = 2.40 \text{ cu.m}$ . For neat cement surface finishing additional 0.2 cu.m (6 bags) of cement will be required.

For 2 cm thick c.c. floor of 1:1½:3 proportion for 100 sq.m. the dry volume of materials as above is equal to 4.125 cu.m. Therefore, cement =  $\frac{4.125}{1+1\frac{1}{2}+3} \times \frac{4.125}{5\frac{1}{2}} = 0.75 \text{ cu.m} = 22.5 \text{ bags}$ , quantity of sand =  $0.75 \times 1\frac{1}{2} = 1.125 \text{ cu.m}$ , and the quantity of stone aggregate =  $0.75 \times 3 = 2.25 \text{ cu.m}$ . For neat cement finishing add extra cement of 0.2 cu.m (6 bags).

For 4 cm thick c.c. 1:2:4 floor 100 sq.m., total dry volume of concrete =  $100 \times 0.04 + 10\%$  (for unevenness) + 50% increase for dry volume =  $4 + 2.2 = 6.6$  cu.m. Therefore, cement =  $\frac{6.6}{1+2+4} \times \frac{6.6}{7} = 0.94 \text{ cu.m}$  (22.2 bags), sand =  $0.94 \times 2 = 1.88 \text{ cu.m}$  and stone aggregate =  $0.94 \times 4 = 3.76 \text{ cu.m}$ . For neat cement finishing add extra cement of 0.2 cu.m (6 bags).

For coloured cement floor, mix pigment colour with neat surface cement in the proportion of 1:3 to 1:6 (colour: cement) to have the desired colour. White cement mixed with colour pigment of the desired proportion may also be used, but for strength it is better if ordinary portland cement is mixed with white cement in the proportion of 1:1 to 1:3 (grey portland cement: white cement) and then to add colour pigment to have the desired colour.

When colour pigment is mixed with white cement, the requirement of colour pigment is much less, may be 1:5 to 1:10 (pigment: white cement).

Ex. 2.5 cm Cement Concrete Floor 1:2:4 unit 1 sq.m. Take - 100 sq.m

Particulars	Quantity	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials -</u>					
stone ballast 20mm gauge (store grade)	2.40 cu.m	1000.00 per cu.m		2400.00	
sand (coarse)	1.20 cu.m	700.00 per cu.m		240.00	
cement (12 bags)	0.60 cu.m	6325.00 per cu.m		3795.00	
cement for surface finishing (6 bags)	0.20 cu.m	6325.00 per cu.m		1265.00	
<u>Labour, etc -</u>				Total =	8300.00
Mistri (Head mason)	2 no.	160.00 per day		120.00	
Mason	10 nos.	150.00 per day		1500.00	
Mazdoor (Beldar)	5 nos.	80.00 per day		400.00	
Boy or woman coolie	5 nos.	70.00 per day		350.00	
Blu sti (including curing)	2 nos.	70.00 per day		140.00	
side borders	Lump sum	90.00 L.S.		90.00	



Total = 2635.00

Add 1 1/2% water charges  
Add 10% contractor's profit

Rate per sqm - Rs. 12192.50/100 = Rs. 122m  
Grand Total: 12192.50 per 100 sqm.

39. 2.5cm Cement Concrete Floor 1:1 1/2:3 unit 1 sqm. Take - 100 sqm.

Particulars	Qty or Nos.	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials</u>					
stone aggregate (grd) 20mm	2.25 cum	1000.00 per cum		2250.00	
sand (coarse)	1.125 cum	700.00 per cum		787.50	
cement (21 bags)	0.75 cum	6325.00 per cum		4743.75	
cement for surface finishing (6 bags)	0.20 cum	6325.00 per cum		1265.00	
Labour - same as for item 32				9046.25	
				2635.00	

Total of materials and labour 11681.25  
Add 1 1/2% water charges 175.20  
Add 10% contractor's profit 1168.10

Rate per sqm - Rs. 13024.55/100 = Rs. 130.00

Grand Total = 13024.55 per 100 sqm.

36. 7.5cm thick lime concrete in floor - 1 sqm. Take - 100 sqm.  
with white lime and Surkhi or sand 1:2 Quantity of L.C. = 100 x 0.075 = 7.5 cum  
Quantity of materials may be calculated proportionately 2/4 of the quantity of 10 cum. from item 1 of part 2.

Particulars	Qty or Nos.	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials</u> -					
Brick ballast 1-class 40mm gully	7.50 cum	400.00 per cum		3000.00	
white lime slaked	1.20 cum	700.00 per cum		840.00	
Surkhi (or sand)	2.40 cum	350.00 per cum		840.00	
<u>Labour, etc</u> -					
Mistri (Head mason)	1/2 no.	160.00 per day		80.00	
Mason	1 no.	150.00 per day		150.00	
Mazdoor (Beldar)	10 nos.	80.00 per day		800.00	
Boy or woman coolie	10 nos.	70.00 per day		700.00	
Ekhasti	1 no.	70.00 per day		70.00	
Sundries T and P, etc.	Lump sum	35.00 L.S.		35.00	
				1835.00	

Total of materials and labour 6515.00  
Add 1 1/2% water charges 97.75  
Add 10% contractor's profit 651.50

Rate per sqm - Rs. 7264.25/100 = Rs. 72.50  
Grand Total 7264.25 per 100 sqm.



Calculation of materials for Mosaic Terrazzo Floor for 100 sq.m.

20mm thick C.C. 1:2:4 - Volume of C.C. =  $100 \times 0.02 + 10\%$  for uneven and rough base =  $2.00 + 0.20 = 2.20 \text{ cu.m.}$  Dry volume =  $2.2 \times 1.50 = 3.3 \text{ cu.m.}$  cement =  $\frac{3.3}{1+2+4} = 0.47 \text{ cu.m. (17 bags)}$

sand =  $0.47 \times 2 = 0.94 \text{ cu.m.}$

stone chips =  $0.47 \times 4 = 1.88 \text{ cu.m.}$

6mm Mosaic Layer 1:1½ - Volume of mosaic concrete =  $100 \times 0.006 + 20\%$  for surface cutting.

by rubbing =  $0.60 + 0.12 = 0.72 \text{ cu.m.}$

Dry volume =  $0.72 + 50\% = 0.72 + 0.36 = 1.08 \text{ cu.m.}$

cement =  $\frac{1.08}{1+1\frac{1}{2}} = \frac{1.08}{2\frac{1}{2}} = 0.4 \text{ cu.m. (12 bags)}$

Marble chips =  $0.4 \times 1\frac{1}{2} = 0.60 \text{ cu.m.}$

Materials for mosaic layer for different proportion -

(i) Proportion 1:1 - Cement = 0.50 cu.m (15 bags), Marble chips = 0.5 cu.m.

(ii) Proportion 1:1½ cement = 0.40 cu.m (12 bags), marble chips = 0.6 cu.m.

(iii) Proportion 1:2 - Cement = 0.36 cu.m (10.8 bags), marble chips = 0.72 cu.m.

(iv) To get whitish base (ground) 10% to 20% of marble dust may be mixed with portland cement.

Mosaic Dado or Skirting - 6mm thick mosaic layer over 20mm thick cement plaster

1:3 cement: coarse sand. Materials for cement mortar same as in para 49. Mosaic layer to be same as above. Labour may be increased by 10% over -

41. Mosaic or Terrazzo Tile Floor - unit 1 sq.m. Take 100 sq.m.

### Materials -

Mosaic Tiles 20cm x 20cm nominal size 2500 nos.

100 sq.m

300.00 per cum

30000.00

20mm lime mortar - white lime (slaked) screed

1 cum

700.00 per cum

700.00

2 cum

350.00 per cum

700.00

cement (for neat cement paste or grout for laying tiles and for joints 6 bags)

0.20 cum

6325.00 per cum

1265.00

Total

32665.00

### Labour etc.

Mistree (Head mason)

1 no.

160.00 per day

160.00

Mason (Specialist)

15 nos.

150.00 per day

2250.00

Mazdoor (Beldar)

15 nos.

20.00 per day

1200.00

Bhisti

1½ nos.

70.00 per day

105.00

Polisher

120 nos.

70.00 per day

8400.00

Polishing stone

L.S.

450.00 L.S.

450.00

Oxalic acid powder

L.S.

90.00 L.S.

90.00

Supplies T. and P. etc.

L.C.

90.00 L.C.

90.00

Total

12745.00

Total of materials and labour

45410.00

681.00

4541.00

Add 1½% water charges

Add 10% Contractor's profit

Grand Total = 50832.00



Brick Floor 10cm thick surface pointed with cement mortar -

Requirement of materials for 100 sq.m. - Brick floor 10 cm thick 100sqm is equal to  $100 \times 0.10 = 10 \text{ cum}$ . Hence materials requirement is same as for 10 cum brickwork but 10% excess mortar may be taken for unevenness of base. For pointing 0.6 cum total dry mortar is required. For brick floor laid with 1:6 cement mortar the quantity of materials are - Brick = 5000 nos, cement = 0.5 cum (15 bags) and sand = 3.0 cum. For pointing 1:2 - cement = 0.2 cum (6 bags) and sand = 0.4 cum are required. Similarly, materials for other proportions may be calculated.

42. Brick Floor 10cm thick cement pointed - unit 1 sq.m. Take - 100 sq.m

(a) Brick laid 1:6 mortar, surface pointed 1:2 cement mortar.

Particulars	Qty or No.	Rate Rs. P.	Cost Rs. P.
<u>Brickwork -</u>			
Materials for brick laying -			
Brick I-class	5000 nos.	2000.00 per cum	10000.00
Cement (15 bags)	0.50 cum	6325.00 per cum	3162.50
Sand local	3.00 cum	400.00 per cum	1200.00
		Total =	14362.50
Labour of brick laying -			
Mistri (Head mason)	$\frac{1}{2}$ no.	160.00 per day	80.00
Mason	10 nos.	150.00 per day	1500.00
Mazdoor (Beldar)	8 nos.	80.00 per day	640.00
Boy or woman coolie	6 nos.	70.00 per day	420.00
Bhisti	1 no.	70.00 per day	70.00
Sundries, T. and P. etc.	Lumpsum	35.00 per s.	35.00
		Total	2745.00
<u>Cement pointing -</u>			
Materials -			
Cement (6 bags)	0.20 cum	6325.00 per cum	1265.00
Sand (local)	0.40 cum	400.00 per cum	160.00
		Total =	1425.00
Labour, etc. -			
Mistri (Head mason)	$\frac{1}{2}$ no.	160.00 per day	80.00
Mason	10 nos.	150.00 per day	1500.00
Mazdoor (Beldar)	10 nos.	80.00 per day	800.00
Bhisti	$\frac{1}{2}$ no.	70.00 per day	35.00
Scaffolding, sundries T and P. etc.	Lumpsum	55.00 L.S.	55.00
		Total	2443.00

Total of materials and labour 3868.00  
 Grand Total 20975.50  
 Add 12% water charges 2517.06  
 Add 10% contractor's profit 2097.55  
 Rs. 23387.60  
 Rate per sq.m. - Rs. 23387.60/100 = Rs. 234.00



45. (i) white washing one coat - unit 1 sq.m. Take - 100 sq.m.

Particulars	Qty in Nos.	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials</u> -					
white lime unslaked @ 400.00 per sq.m	15 kg	4.00 per kg		90.00	
Glue powder	lump sum	5.00 L.S.		5.00	
surrekhi (or sand)	lump sum	5.00 L.S.		5.00	
				<b>Total</b>	<b>50.00</b>
<u>Labour</u> -					
white washer	2 1/2 no.	100.00 per day		66.70	
Boy coolie	2 1/2 no.	70.00 per day		16.70	
Sundries, T. and P. etc	lump sum	5.00 L.S.		5.00	
				<b>Total</b>	<b>118.40</b>

Total materials & labour - 168.40  
Add 10% contractor's profit 16.80

Grand Total: 185.20  
for 100 sq.m.

Rate per sq.m - Rs. 185.20/100 = Rs. 1.85

56. 2cm Thick Damp proof course (D.P.C) with cement mortar 1:2 - unit 1 sq.m. Take - 100 sq.m.

Particulars	Qty in Nos.	Rate		Cost	
		Rs.	P.	Rs.	P.
<u>Materials</u> -					
cement (27 bags)	0.90 cum.	6325.00 per cum		5692.50	
Sand (coarse)	1.80 cum.	700.00 per cum		1260.00	
cem-seal or Impermo (1 kg per bag of cement)	27.00 kg.	40.00 per kg		1080.00	
				<b>Total</b>	<b>2032.50</b>
<u>Labour, etc.</u> -					
Mistrie (Head mason)	1/2 no.	160.00 per day		80.00	
Mason	5 nos.	150.00 per day		750.00	
Mazdoor (Beldar)	5 nos.	20.00 per day		400.00	
Bhist (including curing)	1 no.	70.00 per day		70.00	
Form insides	lump sum	90.00 L.S.		90.00	
Sundries T. and P. etc.	lump sum	35.00 L.S.		35.00	
				<b>Total</b>	<b>1425.00</b>

Total of materials & labour - 9457.50  
Add 1 1/2% water charges 141.90  
Add 10% Contractor's profit 945.75

Grand Total: 10545.15

Rate per sq.m - Rs. 10545.15/100 = Rs. 105.45

for 100 sq.m

77. Asbestos cement sheet ceiling 6mm thick, with 40mm x 20mm teak wood of brading (Excluding frame) - unit 1 sq.m. Take a room 1.50m x 6.30m Area = 28.35 sq.m.

### Materials -

Asbestos cement sheet plain 6mm thick including 5% wastages =  $28.35 + 1.42 = 29.77 \text{ sq.m}$

Teak wood brading assuming 90cm x 90cm panels =  $[(8 \text{ nos} \times 1.5 + 6 \text{ nos} \times 6.30) \times 0.04 \times 0.02] + 10\% \text{ wastages} = 0.065 \text{ cum}$

Screws 50mm  
Screws 60mm  
Nails 50mm

29.77 sq.m	100.00 sq.m	2977.00
------------	-------------	---------

0.065 cum	3000.00 cum	1950.00
200 nos.	60.00 per kg	120.00
450 nos.	60.00 per kg	270.00
1 kg.	30.00/kg	30.00

### Labour, etc.

Mistri (Head mason)

carpenters

Mazdoor (Beldari)

scaffolding

Sundries, T. and P. etc

1/6 no.	160.00 per day	26.70
2 nos.	120.00 per day	240.00
2 nos.	80.00 per day	160.00
Lumpsum	75.00 L.S.	75.00
Lumpsum	30.00 L.S.	30.00

Total of materials & labour = 5878.90  
= 587.90

Add 10% Contractor's profit

Grand Total 6466.60

Rate per sq.m -  $\text{Rs. } 6466.60 / 28.35 = \text{Rs. } 228.00$  for 28.35 sq.m

64. Wood-work in chaukhat or frame - Wrought, framed and fixed - unit 1 cum.

### Salwood work -

Take a frame or chaukhat of 200 x 120 cm door without sill of 8 x 12 cm of salwood

### Materials -

Timber  $5.48 \times 0.08 \times 0.12$  0.053 cum.  
(L =  $2 \times 2.14 + 1 \times 1.2 = 5.48$ )  
Wastage 5% 0.003 cum.  
0.056 cum

### Labour, etc.

Mistri (carpenter)

carpenter

coolie (Helper)

Sundries, T. and P. etc.

1/6 no.	120.00 per day	11.25
3/4 no.	120.00 per day	90.00
1/2 no.	70.00 per day	35.00
Lumpsum	15.00 L.S.	15.00

Total of labour 151.25

Total of materials and labour 1551.25

Add 10% Contractor's profit 155.10

Grand Total 1706.35

Rate per cum (dividing by 0.053) -  $\text{Rs. } 1706.35 / 0.053 = \text{Rs. } 32195.00$



26. 4mm Thick Panelled Door of Indian Teak Wood - unit 1 sqm.  
Take a window shutter 100x150cm (shutter only). Area = 1.5 sqm

Take a window shutter  $100 \times 150 \text{ cm}$  (shutter only). Area =  $1.5 \text{ sq m}$ . (By rule)

Particulars	No.	L m	B m	Thickness m	Qty or nos	Rate		Cost	
						Rs.	P.	Rs.	P.
<b>Materials-</b>									
Timber stiles	4	1.50	0.075	0.04	0.029				
Sash bars vertical (15mm insertion) $L = 150 - (2 \times 7.5) + (2 \times 1.5)$ $= 138\text{cm} = 1.38\text{m}$	2	1.00	0.075	0.04	0.008				
Sash bars horizontal (15mm insertion) = $50 - (2 \times 7.5) + (2 \times 1.5)$ $= 38\text{cm} = 0.38\text{m}$	6	0.38	0.04	0.04	0.003				
Add 5% door wastage					0.035				
Brass fittings —					0.002				
Fittings —					0.037 cum	35000.00		1295.00	
Tower bolt 20cm (upper)	1 no.					70.00 each		70.00	
Tower bolt 15cm (lower)	1 no.					40.00 each		40.00	
Hinges 10cm	4 nos.					6.00 each		24.00	
Brass handle	1 no.					35.00 each		35.00	
wooden cleat	2 nos.					4.00 each		8.00	
Hinges 2.5cm (for wooden cleat)	2 nos.					3.00 each		6.00	
screws 40mm	20 nos.					50.00 per l.no.		10.00	
screws 20mm	50 nos.					25.00 per l.no.		12.50	
Glass panes 26 nos $\times 18.5 \times 33.75\text{ cm} =$ 100 sqm Breadth $= \frac{1}{2}[150 - (2 \times 7.5) - 1 + (2 \times 1.5)]$ Ht. $= \frac{1}{4}[150 - (2 \times 7.5) - (3 \times 1.5) + (2 \times 1.5)] = 33.75\text{ cm}$ putty, and nails for boxing panes	100 sqm					300.00 per sqm		300.00	
Labour, etc —									
Mistri (Carpenter)	1 no.					150.00 per day		150.00	
Carpenters	2 nos.					120.00 per day		240.00	
coolie (helper)	1 no.					70.00 per day		70.00	
putty, glue, etc.	Lumpsum					20.00 L.S.		20.00	
Sundries T. and P. etc.	Lumpsum					15.00 L.S.		15.00	
Total								1825.00	
Total of materials and labour								2195.50	
Add 10% contractor's profit								218.25	
Grand Total								2400.75	
Rate per sqm —								2400.75 / 1.5 = Rs. 1600.50	





Lead and Lift: Normally earthwork is estimated for 30m lead for distance and 1.5m lift for height or depth, and this distance of 30m and the height of 1.5m are known as normal lead and lift. Normal rate for earthwork is for 30m lead and 1.5m lift. For greater lead or lift the rates will be different for every unit of 30m lead and for every unit of 1.5m lift. The earthwork is, therefore, estimated separately for every 30m lead and for every 1.5m lift.

For the calculation of earthwork in a road longitudinal section and cross-section of the ground are taken and the formation line is fixed. The formation line is fixed in consideration of bed level, gradient, height of bank, depth of cutting, etc. In plain countries road is usually in banking, but if the road is in cutting for some other length, the excavated earth from the cutting portion should be utilised for the banking portion within economical limits during the execution of the work. But for estimating of earthwork this point of utilising excavated earth from cutting in certain length in banking of the adjacent may not be taken into account to avoid complicity. In hilly countries road is usually both in banking and in cutting and the excavated earth from cutting is utilised for banking within economical limits.

### Calculation of Lead & Lift:

Cross-section of earthwork of road in banking or in cutting is usually in the form of trapezium, and the quantity of earthwork may be calculated by the following methods:



Sectional area = Area of central rectangular portion + Area of two side triangular portions.

$$= Bd + 2\left(\frac{1}{2}sd \times d\right) = Bd + sd^2$$

$S:1$  is the ratio of side slopes as horizontal:vertical. For 1 vertical, horizontal is  $S$  or  $d$  vertical, horizontal is  $sd$ .

$$\text{Quantity} = (Bd + sd^2) \times L$$

When the ground is in a longitudinal slope, the height of bank or the depth of cutting will be different at the two ends of the section, and mean height or depth may be taken for ' $d$ ' and sectional area at mid-section is taken out for mean height. Alternatively, sectional area at the two ends may be calculated and the mean of two sectional area is taken out. Sectional area at the mid-section or the mean sectional area, multiplied by the length gives the quantity.

$$\text{Mean height} = \frac{d_1 + d_2}{2}$$

Different kinds of soil as sandy, clayey, rocky etc. estimated separately as the rates vary.

Quantity of earthwork may be calculated by the various methods of measurement out of which three methods are given


Method 1. Mid-sectional Area Method: Quantity = Area of mid-section  $\times$  length. Let  $d_1$  and  $d_2$  be the height of bank at two ends portion of embankment,  $L$  the length of the section,  $B$  the formation width and  $S:1$  (horizontal:vertical) the side slope, then



Area of mid section = Area of rectangular portion + area of two triangular portion,  
 $= Bd + \frac{1}{2}sd + \frac{1}{2}sd = Bd + sd$

$\therefore$  Quantity of earthwork =  $(Bd + sd) \times L$

General,  $Q = (Bd + sd^2) \times L$ , where  $d$  stands for mean height or depth.



The quantities of earthwork may be calculated in a tabular form as below.

station or chainage	Depth or Height	Mean Depth or Height $d$	Area of central portion $Bd$	Area of side $sd^2$	Total sectional Area $Bd + sd^2$	Length between stations $L$	Quantity $(Bd + sd^2) \times L$	
							Embankment	Cutting

Area of side sloping surface —

The area of sides which may require fencing or pitching, may be found by multiplying the mean sloping breadth by the length.

The mean sloping breadth =  $\sqrt{(sd^2 + d^2)} = d\sqrt{s^2 + 1}$ , where  $d$  stands for mean  $d$ .

Area of both side slopes =  $2L \times d\sqrt{s^2 + 1}$

This also may be calculated in a tabular form —

station or chainage	Depth or Height	Mean Depth or Height	Breadth of side slopes $d\sqrt{s^2 + 1}$	Length between stations $L$	Total Area of both side slopes $2Ld\sqrt{s^2 + 1}$

Method II - Mean Sectional Area Method:

Quantity = Mean sectional area  $\times$  length,

Sectional area at one end  $A_1 = Bd_1 + sd_1^2$ , sectional area at the other end

$A_2 = Bd_2 + sd_2^2$ ,  $d_1$  and  $d_2$  are the heights or depths at the two ends.

The mean sectional area  $A = \frac{A_1 + A_2}{2}$ , Quantity  $Q = \frac{A_1 + A_2}{2} \times \text{Length}$ .

The quantities of earthwork may be calculated in a tabular form as given below.

station or chainage	Height or Depth $d$	Area of central portion $Bd$	Area of side $sd^2$	Total sectional Area $Bd + sd^2$	Mean sectional Area	Length between stations $L$	Quantity $(Bd + sd^2) \times L$	
							Embankment	Cutting

Method III - Prismoidal Formula method: Quantity or volume =  $\frac{L}{6}(A_1 + A_2 + 4A_m)$

Where  $A_1$  and  $A_2$  are the cross-sectional areas at the two ends of a portion of embankment of a road of length  $L$ , and  $A_m$  is the mid-sectional area.

Let  $d_1$  and  $d_2$  be the heights of banks at the two ends, and  $d_m$  be the mean height at the mid-section,  $B$  be the bottom width and  $s:1$  be the side slope,

cross sectional area at one end -

$$A_1 = Bd_1 + sd_1^2$$

cross-sectional area at other end -

$$A_2 = Bd_2 + sd_2^2$$

cross-sectional area at middle -

$$d_m = \frac{d_1 + d_2}{2}$$

$$A_m = Bd_m + sd_m^2$$

$$= B\left(\frac{d_1 + d_2}{2}\right) + s\left(\frac{d_1 + d_2}{2}\right)^2$$

Quantity =  $\frac{L}{6} (A_1 + A_2 + 4A_m)$

$$= \frac{L}{6} \left[ (Bd_1 + sd_1^2) + (Bd_2 + sd_2^2) + 4 \left\{ B\left(\frac{d_1 + d_2}{2}\right) + s\left(\frac{d_1 + d_2}{2}\right)^2 \right\} \right]$$

$$= \frac{L}{6} \left[ (Bd_1 + Bd_2 + 4B\frac{d_1 + d_2}{2}) + (sd_1^2 + sd_2^2 + 4s\frac{d_1^2 + d_2^2 + 2d_1d_2}{4}) \right]$$




$$= \frac{L}{6} [3Bd_1 + 3Bd_2 + 2sd_1^2 + 2sd_2^2 + 2sd_1d_2]$$

$$= \frac{3BL}{6} (d_1 + d_2) + \frac{2Ls}{6} (d_1^2 + d_2^2 + d_1d_2)$$

$$= \frac{BL}{2} (d_1 + d_2) + \frac{Ls}{3} (d_1^2 + d_2^2 + d_1d_2)$$

$$= \left\{ B\left(\frac{d_1 + d_2}{2}\right) + s\left(\frac{d_1^2 + d_2^2 + 2d_1d_2}{3}\right) \right\} \times L$$

= [Sec. Area of central portion + Sec. Area of side slope portions] x Length.



**Ex. 1** Calculate the quantity of earthwork for 200 metre length for a portion of a road on uniform ground the heights of banks at the two ends being 1.00m and 1.60m. The formation width is 10 metre and side slope 2:1 (horizontal:vertical). Assume that there is no transverse slope.

By method I

$$\text{Quantity} = (B + sd^2) \times \text{Length}$$

$$= (10 \times 1.3 + 2 \times 1.3^2) \times 200$$

$$= (13 + 3.38) \times 200$$

$$= 16.38 \times 200 = 3276 \text{ cu.m.}$$

$$B = 10\text{m}, s = 2, L = 200\text{m}$$

d = mean depth

$$= \frac{1.00 + 1.60}{2} = 1.30\text{m}$$

By method II -

$$A_1 = \text{sec. area at one end} = Bd_1 + sd_1^2 = 10 \times 1 + 2 \times 1^2 = 12 \text{ sq.m.}$$

$$A_2 = \text{sec. area at other end} = Bd_2 + sd_2^2 = 10 \times 1.60 + 2 \times 1.6^2 = 21.12 \text{ sq.m.}$$

$A_m = \text{mid. sec. area}$

$$= Bd_m + sd_m^2 \text{ where } d_m = \frac{d_1 + d_2}{2} = \frac{1.00 + 1.60}{2} = 1.30\text{m}$$

$$= 10 \times 1.30 + 2 \times 1.30^2 = 16.38 \text{ sq.m.}$$

$$\therefore \text{Quantity} = \frac{200}{6} (12 + 21.12 + 4 \times 16.38) = \frac{200}{6} \times 98.64$$

$$= \frac{19728}{6} = 3288 \text{ cu.m.}$$

**Ex. 2** (i) calculate the area of the side slopes of portion of a bank for a length of 200 metres the heights of banks at the two ends being 2.50m and 3.50m and the ratio of the side slope 2:1.

(ii) If the side slopes are to be provided with 15cm thick stone pitching, calculate the cost of pitching at the rate of Rs. 150/- per sq.m.

$$\text{(i) Mean height } d = \frac{2.5 + 3.5}{2} = 3\text{m}$$

$$\text{sloping breadth at the mid-section} = d\sqrt{s^2 + 1} = 3\sqrt{2^2 + 1} = 6.71$$

$$= 2 \times 200 \times 6.71 = 2684 \text{ sq.m.}$$



(ii) Quantity of pitching = Area  $\times$  thickness =  $2684 \times 0.15 = 402.6 \text{ cum}$ .  
Cost of stone pitching =  $402.6 \times 150.00 = \text{Rs. } 60390.00$

### Conveyance Allowance:

When the duty of a government servant is such that it requires extensive travelling at or within a short distance from his headquarters for which no travelling allowance is ordinarily admissible, and he maintains a some sort of conveyance for efficient discharge of his official functions, a Conveyance Allowance per month is granted by the competent authority. The conveyance may be a car, a motor cycle, or a cycle according to the class of officer, and the allowance is meant for the maintenance and upkeep of the conveyance. In the monthly bill a certificate to the effect that the type of conveyance is maintained in a satisfactory condition is to be given. If the officer travels longer distance and draws travelling allowance kilometre (mileage) basis, then his monthly conveyance allowance for that day should be deducted from the duties of the government. If such that he is required to maintain a horse, the conveyance granted to him is known as Horse Allowance.

Conveyance charges means the charges made by the Licensee for the conveyance of gas, "conveyance services" means all services provided by the Licensee of conveying gas to through and within the Licensed Area. "Formula Year" means a year commencing on 1st January. "Network Code" means the network code as prepared by the Licensee.

Conveyance charges means the stamp duty and the registration charges as per provision of the Applicable Law and all incidental and legal costs and expenses for preparation and execution of the Sub-Lease Deed for the transfer of ownership of the Apartment in favour of the Applicant upon completion/Partial completion of the Apartment and clearance of all dues in terms hereof to the company.

Royalty charges: A royalty charge is a payment that a licensee makes to a licensor in exchange for the use of their licensed asset. In construction, this asset could be a new technology, product, system, material or design, perhaps incorporating intellectual property assets like patents, know-how and trademarks. Royalty charges are usually agreed as a percentage of sales generated by the licensed asset. In some circumstances, they are set as a fixed price. Royalty are charged on an ongoing basis.

The amount that the licensee must pay is outlined in a royalty agreement. This agreement also specifies how the licensee may use the licensed asset where they can use it and for how long.



## Abstract cost of estimate

The cost of each item of work is calculated in a tabular form from the quantities already computed and total cost is worked out in abstract of Estimate form. The rates of different items of work are taken as per schedule of rates or current workable rates or analysed rates for finished items of work. A percentage usually 3% of the estimated cost is added to allow for contingencies for miscellaneous petty items which do not come under any classified head of items of work and a percentage of about 2% is provided for exchange of establishment. The Grand Total thus obtained gives the estimated cost of work.

The detailed estimate is usually prepared work-wise, under each sub-work as main building, servants quarters, garage, boundary walls, etc.

The detailed estimate is accompanied with:

- (1) Report
- (2) General specifications
- (3) Detailed specifications
- (4) Drawings: plan, elevation, sectional elevations, detailed drawings, site plan or layout plan or index plan etc.
- (5) Calculation and designs - Design of foundation, beam, slab, lintel, design of channel in case of irrigation channel, design of thickness of metal sheet in case of road etc.
- (6) Analysis of rates, if rates are not as per schedule of rates or for the non-scheduled items.

Valuation :- Valuation is the technique of estimating or determining the basic price or value of a property such as a building, a factory, other engineering structure of various types, land, etc. By valuation the present value of a property is determined. The present value of property may be decided by its selling price, or income or rent it may fetch. The value of property depends on its structure, size, maintenance, location, bank interest, legal control, etc. The value also depends on supply and demand and the purpose for which valuation is required.

Cost means original cost of construction or purchase, while value means the present value (saleable value) which may be higher or lower than the cost. A building whose cost of construction is Rs. 50,000.00, when put for sale may fetch Rs. 60,000.00 this sale price is the value of the building. Similarly, the value may be less than the original cost.

Purpose of valuation :- The main purpose of valuation are as follows

- (i) Buying or Selling Property :- When it is required to buy or to sell a property, its valuation is required.
- (ii) Taxation :- To assess the tax of a property its valuation is required. Taxes may be Municipal Tax, Wealth Tax, Property Tax, etc. and all the taxes are fixed on the valuation of the property.
- (iii) Rent fixation :- In order to determine the rent of a property, valuation is required. Rent is usually fixed on certain percentage of the amount of valuation (5% to 10% of the valuation).
- (iv) Security of loans or Mortgage :- When loans are taken against the security of the property, its valuation is required.
- (v) Compulsory acquisition :- Whenever a property is acquired by law compensation is paid to the owner. To determine the amount of compensation valuation of the property is required.
- (vi) Valuation of a property is also required for Insurance, Betterment charges, specifications, etc.

Cost is the amount incurred in producing and maintaining the product. Value is the utility of a good or service for a customer. By valuation the present value of a property is determined. The present value of property may be decided by its selling price, or income or rent it may fetch. The value of property depends on its structure, size, maintenance, location, bank interest, legal control, etc. The value also depends on supply and demand and the purpose for which valuation is required.



depends on its structure, life, maintenance, location, bank interest etc. Cost means original cost of construction or purchase.

Scrap value: Scrap value is the value of dismantled materials. For a building when the life is over at the end of its utility period the dismantled materials as steel, bricks, timber, etc. will fetch a certain amount which is the scrap value of the building. In the case of machine the scrap value is the value of the metal only or the value of the dismantled parts. The scrap value of a building may be about 10% of its total cost of construction. The cost of dismantling and removal of the rubbish material is deducted from the total receipt from the sale of the useable materials to get the scrap value.

Salvage value: It is the value at the end of the utility period without being dismantled. A machine after the completion of its usual span of life or when it becomes uneconomic may be sold and one may purchase the same for use for some other purpose. The sale value of the machine is the salvage value. It does not include the cost of removal, sale, etc.

Normally, the scrap value, or the salvage value of a property or an asset has got some positive figure, but it may also be zero or negative. As for example the scrap value of a building will be negative as dismantling and removal will be costly.

Assess value: For the purpose of taxation, a property is assessed for its monetary worth. This ascertained price is known as assessed value.

This assessment is done at an annual basis, considering factors such as property value and market conditions in neighboring areas. Governmental agencies like Municipal Corporation conduct this assessment for measuring applicability of property taxes based on the monetary value of the property.

Insurance companies may not use these valuations for indemnities etc. In general, this assessed value tends to be less than the basic or actual market price of the property.

Sinking fund: The fund which is gradually accumulated by way of periodic or annual deposit for the replacement of the building or structure at the end of its useful life, is termed as sinking fund. The object of creating sinking fund is to accumulate sufficient money to meet the cost of construction or replacement of the building or structure after its utility period. The sinking fund is created by regular annual or periodic deposits in compound interest bearing investment, which will form the amount of replacement at the end of the utility period of the property. The sinking fund may be created by taking a sinking fund policy with an insurance company or by depositing in bank to collect highest compound interest. The calculation of sinking fund depends on the life of the building and scrap value of the building or the cost of old materials. The cost of land is not taken into account in calculating sinking fund as land remains intact.

The sinking fund may also be required for payment of loan, if a property is owned or constructed by taking loan. A sinking fund may be created by setting a sum of money annually to accumulate with compound interest in order to repay the debt at the end of the term of loan. The amount thus set aside is also known as Annuity payment. The amount which will be set aside may also be paid directly to lender by way of annual instalment. The amount of annual instalment of the sinking fund may be found out by the formula.

$$I = \frac{S}{(1+i)^n - 1}$$

where  $S$  = total amount of sinking fund to be accumulated,

$n$  = number of years required to accumulate the sinking fund

$i$  = rate of interest in decimal (e.g. 5% = 0.05); and  $I$  = annual instalment required



Ex. 1 A pumping set with a motor has been installed in a building at a cost of Rs. 2,500.00. Assuming the life of the pump as 15 years, work out the amount of annual instalment of sinking fund required to be deposited to accumulate the whole amount of compound interest.

$$\text{The annual sinking fund } I = \frac{S_i}{(1+i)^n - 1} = \frac{2500 \times 0.04}{(1+0.04)^{15} - 1} = 2500 \times 0.05 = \text{Rs. } 125$$

The owner is to deposit Rs. 125/- annually in 4% compound interest carrying investment for 15 years to accumulate Rs. 2,500/-

Ex. 2 An old building has been purchased by a person at a cost of Rs. 30,000/- excluding the cost of the land. Calculate the amount of annual sinking fund at 4% interest assuming the future life of the building as 20 years and the scrap value of the building as 10% of the cost of purchase.

The total amount of sinking fund to be accumulated at the end of 20 years,

$$S = 3000 \times \frac{90}{100} = \text{Rs. } 27,000.00$$

$$\text{Annual instalment of sinking fund } I = \frac{S_i}{(1+i)^n - 1} = \frac{27000 \times 0.04}{(1+0.04)^{20} - 1}$$

$$\text{Annual instalment for sinking fund requires for 20 years} = \text{Rs. } 907.20$$

Depreciation: - Depreciation is the gradual exhaustion of the usefulness of a property. This may be defined as the decrease or loss in the value of a property due to structural deterioration, use, life wear and tear, decay and obsolescence. The value of a building or structure will be gradually reduced due to its use, life wear and tear etc. and a certain percentage of the total cost may be allowed as depreciation to determine its present value. Usually a % on depreciation per annum is allowed. The general annual decrease in the value of a property is known as Annual depreciation. Usually, the percentage rate of depreciation is less at the beginning and gradually increases during later years.

The amount of depreciation being known, the percentage value of a property can be calculated after deducting the total amount of depreciation from the original cost.

Method of calculating depreciation: - The various methods of calculating depreciation are as follows: -

- 1) straight line method
- 2) Constant percentage method
- 3) sinking fund method
- 4) Quantity survey method

In all these methods, it is necessary to decide the economic or effective life of the property.

(1) straight line method: In this method it is assumed that the property loses its value by the same amount every year. A fixed amount of the original cost is deducted every year, so that at the end of the utility period only the scrap value is left.

$$\text{Annual depreciation } D = \frac{\text{Original cost} - \text{Scrap value}}{\text{Life in years}} = \frac{C - S}{n}$$

where C - original cost, S - scrap value, n - life of the property in years and D - annual depreciation. The book value after the number of years, say N years = original cost - NxD.

(2) Constant percentage method or Declining balance method.

In this method, it is assumed that the property will lose its value by a constant percentage of its value at the beginning of every year.

$$\text{Annual depreciation, } D = 1 - \left(\frac{S}{C}\right)^{1/n}, \text{ where } C, S, n \text{ and } D \text{ have the same meaning as above}$$

The value of the property or the depreciated cost at the end of the first year

$$= C - D \quad C_1 = C$$

The value of the property at the end of the 2nd year =  $C_1 - D \quad C_2$  and so on



$$= C \left( \frac{s}{e} \right) \min$$

The formula will fail when  $s = 0$ . When the ratio  $\frac{s}{e}$  is very small, the depreciation over the first year will be considerable.

(2) Sinking fund method: In this method the depreciation of property is assumed to be equal to the annual sinking fund plus the interest on the fund over that year, which is supposed to be invested on interest bearing investments. If  $A$  is the annual sinking fund and  $a, b, c, d$ , etc. represents interest on the sinking fund over subsequent years, and  $C$  = total original cost, then —

At the end of	Depreciation over the year	Total depreciation	Book value
1st year	$A$	$A$	$C - A$
2nd year	$A + b$	$2A + b$	$C - (2A + b)$
3rd year	$A + c$	$3A + b + c$	$C - (3A + b + c)$
$n$ th year	$A + d$	$nA + b + c + d$	$C - (nA + b + c + d)$
			so on

(3) Quantity survey method: In this method the property is studied in detail and loss in value due to life, wear and tear, decay, obsolescence, etc. worked out. Each and every step is based on some logical ground without any fixed percentage of the cost of the property. Only experienced valuers can work the amount of depreciation and present value of property by this method.

Obsolescence: The value of property or structures becomes less by its becoming out of date in style, in structure in design, etc. and this is termed as obsolescence. An old dated building with massive walls, arrangements of rooms not suited in present days and other similar reasons, becomes obsolete even if it is maintained in a very good condition and its value becomes less due to obsolescence. The obsolescence may be due to the reasons such as progress in arts, change in fashions, changes in planning ideas, new inventions, improvements in design technique, etc. A machine of old design may become obsolete, though it may be in good running condition and its value will be less. Thus, though the property is physically sound, it may become functionally inadequate and its economical return becomes less.



# Administrative set up and hierarchy of Engineering Department in different level.

## Office of the Engineer-in-chief (Civil):-

This is the head of department office and functioning under Government of Odisha, Works Department. There are ten Circle officers (seven civil, one P.H., one electrical and one mechanical) functioning under this Organization. There are 36 Civil Divisions and one mechanical Division. 2 S.P.H. Division, 4 General Electrical Divisions and 4 Mechanical Divisions are functioning under the above Circle offices. Sub-Divisional officers and section officers are also functioning under the above Divisional offices.

The Engineer-in-chief (Civil) is the head of the Organization. Three chief Engineers designated as chief Engineer, (CPI & Roads), chief Engineer, Buildings and chief Engineer, World Bank are functioning under the office.

## Design Planning and Investigation & Roads

The Design and planning activity in the organization is provided through a separate Design, planning and investigation wing in the Odisha Works Department. Its head the chief Engineer, Design, planning and investigation and Road (CE(DP & R)) has a reporting responsibility to the EIC-cum-Secretary.

## Buildings:

In addition to responsibilities for roads, Odisha works department has the task of supervising the construction and maintenance of public buildings on behalf of a wide range of state Government Organizations. For this purpose, the organization structure of Odisha works department includes a specific wing devoted to this activity. It is headed by a chief Engineer Buildings (CE(B)) reporting to the EIC-cum-Secretary.

## World Bank Project:

Odisha State Road Project (O.S.R.P.) is a world Bank funded Project implemented by Works Department (OWD) of Govt. The project Development objective (PDO) is to remove transport bottlenecks in targeted transport corridors to generate investment and economic and social development activities in the states of Odisha. The project Management Unit (PMU), headed by chief Engineer (WB) is located at Nimman, South, Unit-5, Bhubaneswar.

## National Highways:

Responsibility for new construction and maintenance works on the National Highway is under the control of the chief engineer national highways (CE NH). The CE (NH) reports to MOST for works carried out on the National Highway network.

## Research Development and Quality Promotion

Inspection and Quality Control activity is under the control of the chief Engineer Research Development and Quality Promotion (CE(RD & QP)). It was established as a Research Laboratory in 1965 to cater to the need for testing of materials involved in road and building construction. This wing's functions expanded in 1982 to include a research development and quality promotion cell.

## Odisha Bridge Construction Corporation

Odisha Bridge & Construction Corporation Limited (OB&CC) was incorporated on 01.01.1983 under Companies Act, 1956 as a Govt. Company. It is a Government Company sponsored by Odisha state Government within the meaning of section 617 of the Companies Act. Since its inception, it is working as a Govt. of Odisha undertaking Organisation. The corporation is governed by Managing Director on behalf of Board of Directors nominated by the Govt. under guidelines set by Memorandum of Association and articles of Association along with work rules mentioned therein.

## Office of the chief Architect:

The office of the chief Architect is working as an independent Head of Department under the administrative control of Works Department and looks after the architectural matters of the state of Odisha. Besides the above, the said office also prepares architectural project drawing for works.



## State Procurement Cell

When the objective of supervision of full roll out of a procurement in the lower Engineering Departments of the state, Government have constituted the State Procurement Cell under the administrative control of works department with IJC Corvill, Odisha as the chief procurement officer and works Department as the secretariat. This wing is headed by chief Engineer cum chief manager (Tech) of the State Procurement Cell, Govt. of Odisha.

### Duties responsibility of chief engineer:

- Communicating the goals of the company to all engineers and professional in the team.
- Supervising every phase of the project from start to completion.
- Calculating costs, material, labour, and time required for each project.
- Approving design and budgets.
- Delegating tasks to engineering teams.
- Supervising staff training as well as equipment installation.
- Performing quality control checks on all systems and products.
- Quickly resolving disputes between staff.
- Acknowledging or rewarding good work.
- Analyzing data and drafting reports for review.

### Duties and responsibility of the Junior Engineer:

- To keep detail history of all roads, culverts, bridges and building which belong to his jurisdiction along with flow of road, conditions of roads, bridges, culverts & buildings.
- To maintain a register with the work which has been executed over the roads, bridges, culverts and building premises or any other structure with relevant data like, Moura Map, Right of way for road stretches, Road furniture, trees, schemes as well as technical details of the asset, air built drawings, nature of any work executed over the asset or its portion, date of completion of the work, end date of defect liability period (DLP) according to the contract for said work, condition of the asset during defect liability period, Name of agency with his contract reference. This register can be road wise/building wise. He is to update asset register on regular basis keeping all relevant drawings linked with the asset in safe custody.
- To inspect every road/bridge/culvert/building on periodic basis. He should maintain a register to keep record as per his inspection and observation. For road stretches this inspection will be bi-weekly basis during monsoon period. If he observes any irregularities or and other identified.
- To watch whether any unlawful matters including encroachment are going on the roads or building premises. If he observes, he should take suitable steps towards it and inform to his higher authority.
- To prepare all the preliminary & detailed estimate for original works, periodical maintenance, addition and alteration as well as modernization as directed by his higher authorities, inclusive of scheduled & Non schedule items with proper analysis of rates, rough drawing, site plan by collecting engineering data and drawings and submit those estimates to his immediate superior authority for approval from competent authority.
- To supervise and see that all works under his charge are done according to the specifications, drawings, standards by given in contract agreement, tender schedule of work and approved sampler by engineers in charge. He is expected to remain at site throughout in order to see that the works are executed properly in accordance with the requirements, standards and approved sampler. It is the duty of the Junior Engineer to bring it at once to the notice of immediate superior authority and also make a



- stipulated period specifications, requirement, drawings, standards laid down and approved samples including quality of materials.
- To see the level of areas where earthwork or similar type of work is under execution and prepare volumetric calculation sheets for quantitative analysis and load charts, etc.
- To carry out test of materials like cement, steel, bitumen, metal, wood, soil, aggregate or any other materials as directed by higher authorities and item of work as specified in contract agreement of work, maintain register of testing of each and every item separately and place to his immediate superior authority to make a note in the register.
- To arrange and issue materials, TSP to contractors/workers at the proper time so that there is no obstruction in the execution of work.
- To keep Government materials, TSP in his custody and care, maintain proper accounts of receipts, issues and balances, arrange adequate watch and ward.

### Duties of Assistance Engineer:

- Designing construction projects by studying project concept, architectural drawings and models.
- Preparing engineering design by collecting and studying reports, maps, drawings, blueprints, aerial photographs and tests on soil composition, terrain, hydrological characteristics and related topographical and geologic data.
- Determining project costs by calculating labor, material, and related costs.
- Preparing feasibility study by analyzing engineering design, conducting environmental impact studies, assembling data.
- Preparing engineering documents by developing construction specifications, plans and schedules.
- Resolving design and development problems.
- Managing budgets and project resources.
- Scheduling material and equipment purchases and deliveries.
- Making sure the project complies with legal requirements, especially health and safety.
- Confirming adherence to construction specifications and safety standards by monitoring project progress, inspecting construction site, verifying calculations and placements.
- Fulfilling project requirements by training and guiding operators.
- Maintaining operations by enforcing project and operational policies and procedures.
- Providing engineering information by answering questions and requests.